

SCHEDULE OF QUANTITIES

40600100 - BITUMINOUS MATERIALS (PRIME COAT) & Z0063804 MICRO-SURFACING, SINGLE PASS, TYPE II, MIXTURE D

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	# OF LINES	LENGTH (FT)	WIDTH (FT)	MICRO-SURFACING AREA (SQ. YD.)	PRIME COAT (GALLONS)
FAP 693 (IL 9)	E.B. & W.B.	889+23	-	900+78	4.0	4620.0	2.0	1026.7	102.7
FAP 693 (IL 9)	E.B. & W.B.	900+78	-	916+58	5.0	7900.0	2.0	1755.6	175.6
FAP 693 SECTION 1 SUBTOTAL =								2782.2	278.2
FAP 693 (IL 9)	SE RAMP	10+27	-	16+58	1.0	631.0	2.0	140.2	14.0
FAP 693 (IL 9)	SE RAMP	10+60	-	16+58	1.0	598.0	2.0	132.9	13.3
FAP 693 (IL 9)	NW RAMP	10+34	-	16+85	1.0	651.0	2.0	144.7	14.5
FAP 693 (IL 9)	NW RAMP	10+62	-	16+52	1.0	590.0	2.0	131.1	13.1
FAP 693 (IL 9)	E.B.	152+86	-	153+39	1.0	53.0	2.0	11.8	1.2
FAP 693 (IL 9)	E.B.	154+17	-	163+17	1.0	900.0	2.0	200.0	20.0
FAP 693 (IL 9)	E.B.	162+52	-	163+12	1.0	60.0	2.0	13.3	1.3
FAP 693 (IL 9)	E.B.	152+86	-	163+17	1.0	1031.0	2.0	229.1	22.9
FAP 693 (IL 9)	E.B.	152+86	-	153+30	1.0	44.0	2.0	9.8	1.0
FAP 693 (IL 9)	E.B.	154+20	-	157+75	1.0	355.0	2.0	78.9	7.9
FAP 693 (IL 9)	E.B.	163+12	-	163+17	1.0	5.0	2.0	1.1	0.1
FAP 693 (IL 9)	E.B.	164+24	-	165+79	1.0	155.0	2.0	34.4	3.4
FAP 693 (IL 9)	E.B.	168+04	-	169+35	1.0	131.0	2.0	29.1	2.9
FAP 693 (IL 9)	E.B.	164+24	-	172+67	1.0	843.0	2.0	187.3	18.7
FAP 693 (IL 9)	E.B.	164+24	-	165+00	1.0	76.0	2.0	16.9	1.7
FAP 693 (IL 9)	E.B.	168+30	-	168+98	1.0	68.0	2.0	15.1	1.5
FAP 693 (IL 9)	E.B.	170+50	-	172+67	1.0	217.0	2.0	48.2	4.8
FAP 693 (IL 9)	E.B.	172+67	-	193+07	2.0	4080.0	2.0	906.7	90.7
FAP 693 (IL 9)	E.B.	179+53	-	185+25	1.0	572.0	2.0	127.1	12.7

▲ REVISED SHEET 4/13/11

* 693 & 704
** (129)-2, (1,2), & (FAP 101)

FILE NAME =	USER NAME = ceerlockbn	DESIGNED BMC	REVISED 4-5-2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
al\p\work\pudot\ceerlockbn\d0243284\	E78892-sht-schedule.dgn	DRAWN BMC	REVISED -		SCALE: N/A	SHEET NO. 1 OF 11 SHEETS	STA. -	TO STA. -	MCLEAN	55	22	
	PLOT SCALE = 48,0000' / 1" =	CHECKED	REVISED -					CONTRACT NO. 70892				
	PLOT DATE = 4/7/2011	DATE 12-20-2010	REVISED -					ILLINOIS FED. AID PROJECT				