

SCHEDULE OF QUANTITIES

70300100 - SHORT-TERM PAVEMENT MARKING (CONT.)

70301000 - WORK ZONE PAVEMENT MARKING REMOVAL (CONT.)

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	# OF LINES	LENGTH (FT.)	AREA (SQ. FT.)
FAP 704 (I-55 BUS)	N.B. & S.B.	230+65	-	279+25	4.0	1944.0	647.4
FAP 704 (I-55 BUS)	S.B.	232+46	-	237+40	1.0	49.4	16.5
FAP 704 (I-55 BUS)	S.B.	232+46	-	238+02	1.0	55.6	18.5
FAP 704 (I-55 BUS)	S.B.	232+89	-	236+19	1.0	33.0	11.0
FAP 704 (I-55 BUS)	N.B.	237+61	-	242+09	1.0	44.8	14.9
FAP 704 (I-55 BUS)	N.B.	237+86	-	241+91	1.0	40.5	13.5
FAP 704 (I-55 BUS)	N.B.	239+06	-	241+26	1.0	22.0	7.3
FAP 704 (I-55 BUS)	N.B.	242+81	-	246+46	2.0	73.0	24.3
FAP 704 (I-55 BUS)	N.B.	247+78	-	251+87	2.0	81.8	27.2
FAP 704 (I-55 BUS)	S.B.	252+15	-	257+33	1.0	51.8	17.2
FAP 704 (I-55 BUS)	S.B.	252+36	-	257+06	1.0	47.0	15.7
FAP 704 (I-55 BUS)	S.B.	253+02	-	256+48	1.0	34.6	11.5
FAP 704 (I-55 BUS)	S.B.	258+78	-	277+05	1.0	73.1	24.3
FAP 704 (I-55 BUS)	N.B.	256+67	-	277+05	1.0	81.5	27.1
FAP 704 (I-55 BUS)	N.B.	271+44	-	277+05	1.0	56.1	18.7
FAP 704 (I-55 BUS)	S.B.	278+37	-	279+25	3.0	26.4	8.8
FAP 704 (I-55 BUS)	N.B. & S.B.	278+67	-	279+25	2.0	11.6	3.9
FAP 704 (I-55 BUS) TOTAL =						2726.2	907.8
TOTAL =						8274.9	2755.5
USE =						8275.0	2756.0

▲ REVISED SHEET 4/13/11

• 693 & 704
** (129)I-2, (L2)I, & (FAP 10)I

FILE NAME =	USER NAME = cealockbm	DESIGNED BMC	REVISED 4-5-2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\p\dot\cealockbm\08243284\70892-shr-schedule.dgn		DRAWN BMC	REVISED -		SCALE: N/A	SHEET NO. 8 OF 11 SHEETS	STA. -	TO STA. -	MCLEAN	55	29	
PLOT SCALE = 48,0000' / 1".		CHECKED -	REVISED -		FED. ROAD DIST. NO.			(ILLINOIS) FED. AID PROJECT				
PLOT DATE = 4/7/2011		DATE 12-20-2010	REVISED -		CONTRACT NO. 70892							