

SCHEDULE OF QUANTITIES

78300100 PAVEMENT MARKING REMOVAL

4" SKIP DASH LINES (WHITE)

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	# OF LINES	LENGTH (FT.)	AREA (SQ. FT.)
FAP 693 (IL 9)	E.B. & W.B.	889+23	-	907+58	2.0	917.5	305.5
FAP 693 (IL 9)	W.B.	906+79	-	907+58	1.0	19.8	6.6
FAP 693 (IL 9)	E.B. & W.B.	909+22	-	916+58	3.0	552.0	183.8
FAP 693 SECTION 1 SUBTOTAL =							495.9
FAP 693 (IL 9)	NW RAMP	10+62	-	16+24	1.0	140.5	46.8
FAP 693 (IL 9)	NW RAMP	11+16.5	-	16+85	1.0	142.1	47.3
FAP 693 (IL 9)	SE RAMP	10+78	-	16+58	1.0	145.0	48.3
FAP 693 (IL 9)	SE RAMP	10+88	-	16+58	1.0	142.5	47.5
FAP 693 (IL 9)	E.B.	152+86	-	163+12	1.0	256.5	85.4
FAP 693 (IL 9)	W.B.	153+00	-	157+06	1.0	101.5	33.8
FAP 693 (IL 9)	E.B.	155+79	-	157+87	1.0	52.0	17.3
FAP 693 (IL 9)	W.B.	159+21	-	163+12	1.0	97.8	32.6
FAP 693 (IL 9)	E.B./W.B.	173+55	-	183+54	2.0	499.5	166.3
FAP 693 (IL 9)	E.B./W.B.	185+19	-	190+24	2.0	252.5	84.1
FAP 693 (IL 9)	E.B./W.B.	191+08	-	193+07	2.0	99.5	33.1
FAP 693 SECTION 2 SUBTOTAL =							642.5
FAP 693 (IL 9)	E.B.	129+29	-	130+50	1.0	30.3	10.1
FAP 693 (IL 9)	E.B.	131+75	-	143+82	1.0	301.8	100.5
FAP 693 (IL 9)	E.B.	144+89	-	157+00	1.0	302.8	100.8
FAP 693 (IL 9)	E.B.	158+20	-	183+11	1.0	622.8	207.4
FAP 693 (IL 9)	E.B.	184+22	-	198+58	1.0	359.0	119.5
FAP 693 (IL 9)	W.B.	129+29	-	143+82	1.0	363.3	121.0
FAP 693 (IL 9)	W.B.	144+89	-	156+84	1.0	298.8	99.5
FAP 693 (IL 9)	W.B.	158+13	-	183+11	1.0	624.5	208.0
FAP 693 (IL 9)	W.B.	184+22	-	203+15	1.0	473.3	157.6
FAP 693 (IL 9)	W.B.	204+77	-	212+35	1.0	189.5	63.1
FAP 693 SECTION 3 SUBTOTAL =							1187.4

78300100 PAVEMENT MARKING REMOVAL (CONT.)

4" SKIP DASH LINES (WHITE) (CONT.)

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	# OF LINES	LENGTH (FT.)	AREA (SQ. FT.)
FAP 704 (I-55 BUS)	N.B. & S.B.	230+65	-	231+00	4.0	35.0	11.7
FAP 704 (I-55 BUS)	S.B.	232+46	-	241+36	2.0	445.0	148.2
FAP 704 (I-55 BUS)	N.B.	232+81	-	241+91	2.0	455.0	151.5
FAP 704 (I-55 BUS)	S.B.	232+89	-	236+19	1.0	82.5	27.5
FAP 704 (I-55 BUS)	N.B.	238+87	-	241+26	1.0	59.8	19.9
FAP 704 (I-55 BUS)	S.B.	242+40	-	246+46	2.0	203.0	67.6
FAP 704 (I-55 BUS)	N.B.	242+81	-	246+46	2.0	182.5	60.8
FAP 704 (I-55 BUS)	S.B.	247+78	-	251+48	3.0	277.5	92.4
FAP 704 (I-55 BUS)	N.B.	247+78	-	251+87	2.0	204.5	68.1
FAP 704 (I-55 BUS)	S.B.	252+36	-	277+05	2.0	1234.5	411.1
FAP 704 (I-55 BUS)	N.B.	253+02	-	277+05	2.0	1201.5	400.1
FAP 704 (I-55 BUS)	S.B.	253+02	-	256+48	1.0	86.5	28.8
FAP 704 (I-55 BUS)	S.B.	278+37	-	279+25	2.0	44.0	14.7
FAP 704 (I-55 BUS)	N.B. & S.B.	278+67	-	279+25	2.0	29.0	9.7
FAP 704 (I-55 BUS) TOTAL =							1511.9
4" SKIP-DASH (WHITE) TOTAL =							3837.7

4" SKIP-DASH (YELLOW)

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	# OF LINES	LENGTH (FT.)	AREA (SQ. FT.)
FAP 693 (IL 9)	E.B. & W.B.	889+23	-	905+84	2.0	830.5	276.6
FAP 693 (IL 9)	E.B. & W.B.	905+84	-	907+58	1.0	43.5	14.5
FAP 693 SECTION 1 SUBTOTAL =							291.0
FAP 704 (I-55 BUS)	-	-	-	-	-	-	-
4" SKIP-DASH (YELLOW) TOTAL =							291.0

▲ SHEET ADDED

4/13/11

• 693 & 704
** (129)I-2, (1,2)I, & (FAP 10)I

FILE NAME =	USER NAME = ceer-lockbn	DESIGNED BMC	REVISED 4-5-2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ce:\p\work\p\dot\ceerlockbn\id243284\678992-sht-schedule.dgn	678992-sht-schedule.dgn	DRAWN BMC	REVISED -		SCALE: N/A	SHEET NO. 110 OF 11 SHEETS	STA. -	TO STA. -	•	••	MCLEAN	55	320
PLOT SCALE = 48.0000 / in.		CHECKED -	REVISED -					CONTRACT NO. 70892					
PLOT DATE = 4/7/2011		DATE 12-20-2010	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								