

SCHEDULE OF QUANTITIES

78300200 - RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL (CONT.)

70004005 - FIBER ASPHALT

4" SOLID (WHITE) WITH SINGLE BRPMS (FAP 704)

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	LENGTH (FT.)	# OF LINES	ONE-WAY CRYSTAL (EACH)	TWO-WAY AMBER (EACH)	ONE-WAY AMBER (EACH)
FAP 704 (I-55 BUS)	S.B.	232+46	-	237+40	494.0	1.0	13	-	-
FAP 704 (I-55 BUS)	S.B.	232+46	-	238+02	556.0	1.0	14	-	-
FAP 704 (I-55 BUS)	N.B.	237+61	-	242+09	448.0	1.0	12	-	-
FAP 704 (I-55 BUS)	N.B.	237+86	-	241+91	405.0	1.0	11	-	-
FAP 704 (I-55 BUS)	N.B.	242+81	-	246+46	365.0	1.0	10	-	-
FAP 704 (I-55 BUS)	S.B.	247+78	-	251+48	370.0	1.0	10	-	-
FAP 704 (I-55 BUS)	S.B.	252+15	-	257+33	518.0	1.0	13	-	-
FAP 704 (I-55 BUS)	S.B.	252+36	-	257+06	470.0	1.0	12	-	-
FAP 704 (I-55 BUS)	N.B.	271+44	-	277+05	561.0	1.0	14	-	-
FAP 704 (I-55 BUS) SUBTOTAL =							109	-	-
FAP 704 (I-55 BUS) TOTAL =							639	-	-
PROJECT TOTAL =							1371	207	7
USE =							1371	207	7

LOCATION	STATION	TO	STATION	# OF LINES	LENGTH (FT.)	% THAT REQUIRES FIBER	FIBER ASPHALT (LBS)
FAP 693 (IL 9)	889+23	-	897+31	4.0	3232.0	25.0%	331.3
FAP 693 (IL 9)	897+31	-	908+42	4.0	4444.0	50.0%	911.0
FAP 693 (IL 9)	900+78	-	908+42	1.0	764.0	50.0%	156.6
FAP 693 (IL 9)	908+42	-	916+58	5.0	4080.0	25.0%	418.2
FAP 693 SECTION 1 SUBTOTAL =							1817.1
FAP 704 (I-55 BUS)	248+31	-	251+97	2.0	732.0	50.0%	150.1
FAP 704 (I-55 BUS) SUBTOTAL =							150.1
PROJECT TOTAL =							1967.2
USE =							1968.0

▲ SHEET ADDED 4/13/11

• 693 & 704
•• (129)I-2, (1,2)I, & (FAP 10)I

FILE NAME =	USER NAME = ceerlookim	DESIGNED BMC	REVISED 4-5-2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pw\work\pwidot\ceerlookim\12243284\570892-sht-schedule.dgn		DRAWN BMC	REVISED -		SCALE: N/A	SHEET NO. 111 OF 11 SHEETS	STA. -	TO STA. -	*	**	MCLEAN	55	321
		CHECKED -	REVISED -		CONTRACT NO. 70892								
		DATE 12-20-2010	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								