

SUMMARY OF QUANTITIES

I-55 BUS

LOCATION:	FAP 693 (IL 9) FAP 704 (VETERANS PKWY) FAP 693 (IL 9)	
	MCLEAN CO. MCLEAN CO. MCLEAN CO.	
	STA. 889+23 STA. 230+65 *STA. 152+86	
	TO TO TO	
	STA. 916+58 STA. 279+25 *STA. 172+67	
	URBAN URBAN URBAN	
	100% STATE 100% STATE 100% STATE	

* NOTE: N.W. RAMP : STA. 10+00 TO 17+11.23 & S.E. RAMP: STA. 10+00 TO 17+08.86 ARE INCLUDED.

CONSTRUCTION CODE: 0005 0005 0005

PAY ITEM CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL	QTY.	QTY.	QTY.
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1251.0	278.0	737.0	236.0
67100100	MOBILIZATION	LSUM	1.0	0.3	0.4	0.3
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4771.0	1252.0	2727.0	792.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1589.0	417.0	908.0	264.0
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	24144.0	8128.0	12819.0	3197.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1041.0	194.0	641.0	206.0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	8029.0	2707.0	4258.0	1064.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1028.0	181.0	641.0	206.0
X0326240	MICRO-SURFACING TEST STRIP	EACH	1.0	0.3	0.4	0.3
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1.0	0.3	0.4	0.3
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	30.0		20.0	10.0
Z0026346	NIGHTTIME WORK ZONE LIGHTING	LSUM	1.0		0.7	0.3
Z0004005	FIBER ASHPALT	POUND	1968.0	1818.0	150.0	
Z0063804	MICRO-SURFACING, SINGLE PASS, TYPE II, MIXTURE D	SQ YD	12508.0	2782.0	7364.0	2362.0

*SPECIALTY ITEM

FILE NAME *	USER NAME = ceerlockbm	DESIGNED BMC	REVISED -	STATE OF ILLINOIS	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cc:\pwwork\pwwork\ceerlockbm\d0243284\670892-sht-500.dgn	670892-sht-500.dgn	DRAWN BMC	REVISED -	DEPARTMENT OF TRANSPORTATION		.	**	MCLEAN	55	05
PLOT SCALE = 40.0000 / IN.	CHECKED -	REVISOR -	REVISED -		SCALE: -	SHEET NO. 1 OF 1 SHEETS	STA. -	TO STA. -	CONTRACT NO. 70892	
PLOT DATE = 12/29/2010	DATE 12-22-10	REVISOR -	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	

* 693 & 704
** (1291-2 & (1,2) & (FAP 10)1