

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	STP(L25) 0005 CONSTR. CODE ROADWAY 80% FEDERAL 20% STATE	HSIP (LS3E) 0021 CONSTR. CODE SAFETY SHOULDERS 90 % FEDERAL 10 % STATE
PAY CODE NUMBER	PAY ITEM DESCRIPTION				
20200600	EXCAVATING AND GRADING EXISTING SHOULDERS	UNIT	970	686	284
28100825	STONE DUMPED RIPRAP, CLASS B3	TON	60	60	-
28200200	FILTER FABRIC	SQ YD	65	65	-
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	4	4	-
35400100	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 6"	SQ YD	4.2	4.2	-
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	108	108	-
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	192	192	-
40600300	AGGREGATE (PRIME COAT)	TON	999.3	999.3	-
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	7332	7332	-
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	987	987	-
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1101	1101	-
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	122.2	122.2	-
40600990	TEMPORARY RAMP	SQ YD	38	38	-
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	19663	19246	417
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2757	2114	643
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	120	120	-
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	122.5	122.5	-
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	15139	15139	-
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	624	624	-