

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		90% FEDERAL 10% STATE 0004
20200100	EARTH EXCAVATION	CU YD	357	357
20400800	FURNISHED EXCAVATION	CU YD	3702	3702
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1530	1530
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	93	93
28000305	TEMPORARY DITCH CHECKS	FOOT	6	6
28000500	INLET AND PIPE PROTECTION	EACH	6	6
35101400	AGGREGATE BASE COURSE, TYPE B	TON	2064	2064
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	9063	9063
44004250	PAVED SHOULDER REMOVAL	SQ YD	3439	3439
48101200	AGGREGATE SHOULDERS, TYPE B	TON	854	854
54246405	INLET BOX, STANDARD 542531	EACH	2	2
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	600	600
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	55	55
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15
70300100	SHORT TERM PAVEMENT MARKING	FOOT	103	103
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2579	2579
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	34	34
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2579	2579
X0301893	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE DRAIN	EACH	7	7
X0584500	DRUMS	EACH	38	38
*X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.9	0.9

* SPECIALTY
ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN -	REVISED -		70	(18-47)	CUMBERLAND	47	3				
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE: NA			SHEET NO. 1 OF 1 SHEETS			CONTRACT NO. 74481		
	PLOT DATE = #DATE#	DATE -	REVISED -		STA. TO STA.			ILLINOIS FED. AID PROJECT					