

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE 0014		
25100630	EROSION CONTROL BLANKET	SQ YD	1207	1207		
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	1889	1889		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2267	2267		
50102400	CONCRETE REMOVAL	CU YD	88	88		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	88	88		
50300300	PROTECTIVE COAT	SQ YD	152	152		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4150	4150		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7120	7120		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	308	308		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	10	10		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10	10		
52100520	ANCHOR BOLTS, 1"	EACH	40	40		
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	1862	1862		
60607500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24 (ABUTTING EXISTING PAVEMENT)	FOOT	403	403		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	2418	2418		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4711	4711		
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4406	4406		
*78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	504	504		
*78100300	REPLACEMENT REFLECTOR	EACH	95	95		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1849	1849		
X0325299	INLET MODIFICATION	EACH	2	2		
*X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.25	0.25		
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	2418	2418		
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	13316	13316		
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	35	35		
*X7830050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	95	95		
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	20	20		

\*SPECIALTY ITEM

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pw_work\pwidot\teasleyck\d0209576\07	4491-sh1-soq.dgn	DRAWN -	REVISED -			320	.	Macon	32	3	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 74491					
	PLOT DATE = 2/24/2011	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.