

**STAGE 1**

COMBINATION CURB & GUTTER REMOVAL	
STA 980+26 TO 984+74	900 FOOT
LT STA 998+89 TO LT 1002+48	595 FOOT
RT STA 1000+82 TO LT 1004+83	401 FOOT
TOTAL	1896 FOOT

CONCRETE MEDIAN SURFACE REMOVAL	
STA 980+29 TO 981+65	804 SQ FT
STA 983+61 TO 984+71	549 SQ FT
STA 1003+71 TO 1004+80	546 SQ FT
TOTAL	1899 SQ FT

INLET MODIFICATION	
STA 984+69	1 EACH
TOTAL	1 EACH

PCC BASE COURSE 9"	
STA 980+26 TO 984+74	703 S. Y.
STA 998+64 TO 1004+83	920 S. Y.
TOTAL	1623 S. Y.

**STAGE 2**

COMBINATION CURB & GUTTER REMOVAL	
LT STA 978+40 TO 979+74	146 FOOT
RT STA 998+60 TO 1000+82	222 FOOT
TOTAL	368 FOOT

CONCRETE MEDIAN SURFACE REMOVAL	
STA 978+64 TO 979+71	519 SQ FT
TOTAL	519 SQ FT

INLET MODIFICATION	
STA 979+69	1 EACH
TOTAL	1 EACH

PCC BASE COURSE 9"	
STA 978+33 TO 979+74	129 S. Y.
STA 998+60 TO 1000+82	137 S. Y.
TOTAL	266 S. Y.

**AFTER STAGE 2**

COMB. CONC. C&G TYPE B6.24 (ABUTTING EX. PAVT.)	
LT STA 978+40 TO 979+74	146 FOOT
STA 980+26 TO 984+74	900 FOOT
LT STA 1000+76 TO 1004+83	408 FOOT
RT STA 1000+76 TO 1004+83	408 FOOT
TOTAL	1862 FOOT

COMB. CONC. C&G TYPE B9.24 (ABUTTING EX. PAVT.)	
LT STA 998+89 TO 1000+76	187 FOOT
RT STA 998+60 TO 1000+76	216 FOOT
TOTAL	403 FOOT

NOTE: TRANSITION B9.24 TO B6.24 STA 1000+51 TO STA 1000+76  
SEE GENERAL NOTES

CONC. MEDIAN SURFACE 4"	
STA 978+64 TO 979+71	519 SQ FT
STA 980+29 TO 981+65	804 SQ FT
STA 983+61 TO 984+71	549 SQ FT
STA 1003+71 TO 1004+80	546 SQ FT
TOTAL	2418 SQ FT

SEEDING, CLASS 2 (SPECIAL)	
STA 981+65 TO 983+61	0.06 ACRE
STA 998+63 TO 1003+71	0.19 ACRE
TOTAL	0.25 ACRE

EROSION CONTROL BLANKET	
STA 981+65 TO 983+61	299 SQ YD
STA 998+63 TO 1003+71	908 SQ YD
TOTAL	1207 SQ YD

PAVEMENT MARKING

SEQUENCE & LOCATION	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	PAINT PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING - LINE 6"	REPLACEMENT REFLECTOR	WORK ZONE PAVEMENT MARKING REMOVAL
UNITS	SQ FT	EACH	FOOT	FOOT	FOOT	FOOT	EACH	SQ FT
<b>STAGE 1</b>								
LINE BESIDE WB LTL STA 1005+93 TO 1008+35	121	7						
LINE BESIDE MEDIAN RT STA 977+75 TO 985+29	381							
LINE BESIDE MEDIAN RT STA 1002+67 TO 1004+82	72							
LINE BESIDE MEDIAN LT STA 982+37 TO 987+28	164							
LINE BESIDE MEDIAN LT STA 998+94 TO 1004+83	196							
SKIP DASHES BETWEEN EB LANES STA 974+60 TO 978+20	30	4						
SKIP DASHES BETWEEN WB LANES STA 979+75 TO 1011+30	263	41						
DOUBLE YELLOW BETWEEN LANES LT STA 979+77 TO 999+64			3974					
WHITE TAPER LINE STA 974+59 TO 987+26			1267					
YELLOW TAPER LINE STA 999+08 TO 1005+16			608					
YELLOW TAPER LINE STA 999+64 TO 1004+81			517					
<b>AFTER STAGE 1</b>								2325
WET REFLECTIVE TEMPORARY TAPE								
<b>STAGE 2</b>								
LINE BESIDE EB LTL STA 990+47 TO 993+09	131	8						
LINE BESIDE MEDIAN RT STA 998+75 TO 1002+67	130							
LINE BESIDE MEDIAN LT STA 978+32 TO 982+37	135							
SKIP DASHES BETWEEN EB LANES STA 978+20 TO 1005+30	226	35						
DOUBLE YELLOW BETWEEN LANES STA 985+27 TO 1005+29			4004					
YELLOW TAPER LINE STA 975+70 TO 985+27			957					
YELLOW TAPER LINE STA 978+32 TO 985+27			695					
WHITE TAPER LINE STA 998+75 TO 1011+29			1254					
STOP BAR STA 993+35 TO 993+70				35				
YELLOW "CAT TRACKS" STA 993+70 TO 993+90			40					
<b>AFTER STAGE 2</b>								2386
WET REFLECTIVE TEMPORARY TAPE								
<b>FINAL</b>								
YELLOW LINE BESIDE MEDIAN RT STA 977+75 TO 985+29					754			
YELLOW LINE BESIDE MEDIAN RT STA 998+75 TO 1004+82					607			
YELLOW LINE BESIDE MEDIAN LT STA 978+32 TO 987+32					900			
YELLOW LINE BESIDE MEDIAN LT STA 998+94 TO 1004+83					589			
SOLID WHITE BESIDE LTL STA 990+47 TO 993+09						262	8	
SOLID WHITE BESIDE LTL STA 1005+93 TO 1008+35						242	7	
WHITE SKIP DASHES BETWEEN EB LANES STA 974+60 TO 1005+30					767		39	
WHITE SKIP DASHES BETWEEN WB LANES STA 979+75 TO 1011+30					789		41	
<b>TOTALS</b>	1849	95	13316	35	4406	504	95	4711