

STAGE 1

PCC BASE COURSE 9"	
STA 44+00 TO 46+65	177 S. Y.
STA 53+43 TO 56+10	178 S. Y.
TOTAL	355 S. Y.

COMBINATION CURB & GUTTER REMOVAL	
STA 44+00 TO 46+65	530 FOOT
STA 53+43 TO 56+10	534 FOOT
TOTAL	1064 FOOT

REMOVE & REFLECT EXISTING SIGN	
STA 44+26	1 EACH
STA 48+60	1 EACH
STA 51+38	1 EACH
STA 55+84	1 EACH
TOTAL	4 EACH

CONCRETE MEDIAN REMOVAL	
STA 43+95 TO 44+00	35 SQ FT
STA 56+11 TO 56+16	35 SQ FT
TOTAL	70 SQ FT

CONCRETE MEDIAN SURFACE REMOVAL	
STA 44+00 TO 46+65	636 SQ FT
STA 53+43 TO 56+10	641 SQ FT
TOTAL	1277 SQ FT

AFTER STAGE 2

COMB. CONC. C&G TYPE M6.12 (ABUTTING EX. PAVT.)	
STA 44+00 TO 46+65	530 FOOT
STA 53+43 TO 56+10	534 FOOT
TOTAL	1064 FOOT

CONC. MEDIAN SURFACE 4"	
STA 44+00 TO 46+65	636 SQ FT
STA 53+43 TO 56+10	641 SQ FT
TOTAL	1277 SQ FT

CONCRETE MEDIAN, TYPE SM.	
STA 43+95 TO 44+00	35 SQ FT
STA 56+11 TO 56+16	35 SQ FT
TOTAL	70 SQ FT

PAVEMENT MARKING SCHEDULE

SEQUENCE & LOCATION	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	WET REFLECTIVE TEMPORARY TAPE LETTERS AND SYMBOLS	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	PRISMATIC CURB REFLECTOR	REPLACEMENT REFLECTOR	WORK ZONE PAVEMENT MARKING REMOVAL
UNITS	SQ FT	EACH	SQ FT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	SQ FT	FOOT	FOOT	EACH	EACH	SQ FT
STAGE 1															
ARROWS IN SB LTL	62.4		31.2												
ARROWS IN NB LTL	46.8		31.2												
LINE BESIDE SB LTL	137.5	8													
LINE BESIDE NB LTL	119.5	7													
LINE BESIDE MEDIAN STA 43+97 TO 46+67	180														
LINE BESIDE MEDIAN STA 53+76 TO 56+15	177.3														
SKIP DASHES BETWEEN SB LANES	170.5	18													
DOUBLE YELLOW BETWEEN LANES STA 43+75 TO 56+17				2544											
WHITE TAPER LINE STA 43+65 TO 48+15				450											
WHITE TAPER LINE STA 53+50 TO 56+80				330											
YELLOW "CAT TRACKS" STA 56+17 TO 56+90				33											
WHITE LINE DEFINING LTL STA 43+75 TO 44+85					110										
WHITE LINE DEFINING LTL STA 54+95 TO 56+17					91										
STOP BAR STA 43+75						12									
STOP BAR STA 56+17						12									
AFTER STAGE 1															1330
WET REFLECTIVE TEMPORARY TAPE															
STAGE 2															
SKIP DASHES BETWEEN NB LANES	170.5	18													
ARROWS IN LTL			62.4												
DOUBLE YELLOW BETWEEN LANES STA 43+85 TO 56+40				2580											
WHITE TAPER LINE STA 43+40 TO 46+67				327											
WHITE TAPER LINE STA 52+00 TO 56+38				438											
YELLOW "CAT TRACKS" STA 43+30 TO 43+85				27											
WHITE LINE DEFINING LTL STA 43+85 TO 45+07					92										
WHITE LINE DEFINING LTL STA 55+20 TO 56+40					120										
STOP BAR STA 43+85						12									
STOP BAR STA 56+40						12									
AFTER STAGE 2															1340
WET REFLECTIVE TEMPORARY TAPE															
ARROWS IN LEFT TURN LANES							109.2								
YELLOW LINE BESIDE MEDIAN								1072							
WHITE LINE BESIDE SB LTL STA 43+97 TO 46+72									275						
WHITE LINE BESIDE NB LTL STA 53+76 TO 56+15									239						
WHITE SKIP DASHES BETWEEN LANES NB & SB									682						
FINAL															1063
TEMPORARY PAVEMENT MARKINGS															
SB LEFT TURN LANE										62.4					
NB LEFT TURN LANE										46.8					
WHITE EDGE LINES STA 43+30 TO 56+90											2720				
YELLOW LINE BESIDE MEDIAN											1072				
SOLID WHITE BESIDE LTL STA 43+97 TO 46+72												275		8	
SOLID WHITE BESIDE LTL STA 53+76 TO 56+15												239		7	
WHITE SKIP DASHES BETWEEN LANES STA 43+25 TO 56+89												682		36	
REPLACED MEDIAN													50		
TOTALS	1064	51	124.8	6729	413	48	109.2	1072	1196	109.2	3792	1196	50	51	3733

FILE NAME = c:\pw\work\pvidot\teasleyok\30209700\07

USER NAME = teasleyok
4494-ah-t-schedule.dgn

DESIGNED -
DRAWN -

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES

F.A.P. RTE. 832 SECTION COUNTY TOTAL SHEETS SHEET NO. 3/5

CONTRACT NO. 74494