

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

URBAN

80% FEDERAL
20% STATE

TOTAL QUANTITIES	0005 ALTON 3P	0005 MADISON COUNTY 3P	0004 MADISON COUNTY 3R
------------------	---------------	------------------------	------------------------

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 ALTON 3P	0005 MADISON COUNTY 3P	0004 MADISON COUNTY 3R
60500105	FILLING MANHOLES	EACH	17			17
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	2200	2200		
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	2470	1920	550	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	16600	12800	3800	
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	950	175	775	
63000015	STEEL PLATE BEAM GUARDRAIL, TYPE D	FOOT	175		175	
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2		2	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	2	2	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	2	2	
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2		2	
63200310	GUARDRAIL REMOVAL	FOOT	2,200	252	450	1,498
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	6	2	2
67100100	MOBILIZATION	L SUM	1	0.6	0.2	0.2
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.6	0.2	0.2
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	1	0.6	0.2	0.2
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.6	0.2	0.2
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.6	0.2	0.2
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.6	0.2	0.2
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	15		45
70300100	SHORT TERM PAVEMENT MARKING	FOOT	15756	13356	720	1680
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,360.2	923.4	62.4	374.4
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	112,989	88012	11257	13,720
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1756	1756		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	879.4	693	62.4	124
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1313	1113	60	140
* 72000100	SIGN PANEL - TYPE 1	SQ FT	36			36
* 73000100	WOOD SIGN SUPPORT	FOOT	60			60
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,360.2	923.4	62.4	374.4
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	112,989	88012	11,257	13,720

* SPECIALTY ITEM

REVISD 4/13/11

FILE NAME =
USER NAME = karlesal
DESIGNED -
DRAWN -
PLOT SCALE = 58.8800' / IN.
PLOT DATE = 2/7/2011

REVISD -
REVISD -
REVISD -
REVISD -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	(132-2,3,4 133-1)RS	MADISON	122	5

CONTRACT NO. 76B80
ILLINOIS FED. AID PROJECT