

CLASS A PATCHING

MILE STATION (MI.)	DIRECTION (EB / WB)	LANE DESCRIPTION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	TYPE II (SQ YD) 5 to 15	TYPE III (SQ YD) 15 to 25	TYPE IV (SQ YD) 25+	SAW CUTS (FT)	TIE BARS (EACH)	PATCHING REINFORCEMENT (SQ YD)
2.46	WB	PL	20	12	26.7			26.7	88	10	26.7
2.46	WB	DL	20	12	26.7			26.7	88	10	26.7
2.45	WB	PL	12	12	16.0		16.0		72		16.0
2.45	WB	DL	12	12	16.0		16.0		72		16.0
2.49	WB	PL	30	12	40.0			40.0	108		40.0
2.49	WB	DL	30	12	40.0			40.0	108		40.0
2.51	WB	PL	40	12	53.3			53.3	128	20	53.3
2.51	WB	DL	40	12	53.3			53.3	128	20	53.3
2.52	WB	DL	35	12	46.7			46.7	118	18	46.7
2.53	WB	PL	15	12	20.0		20.0		78		20.0
2.53	WB	DL	15	12	20.0		20.0		78		20.0
2.54	WB	PL	25	12	33.3			33.3	98		33.3
2.54	WB	DL	25	12	33.3			33.3	98		33.3
1.22	EB	2ND LANE	25	12	33.3			33.3	98		33.3
1.41	EB	RT LANE	80	12	106.7			106.7	208	40	106.7
2.68	EB	RT LANE	60	12	80.0			80.0	168	30	80.0
2.75	EB	RT LANE	10	12	13.3	13.3			68		13.3
3.08	EB	RT LANE	60	12	80.0			80.0	168	30	80.0
TOTALS						13.3	72.0	653.3	1972	178	738.6

▲ REVISED SHEET 4/13/11

FILE NAME =	USER NAME = karlasal	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et\pw_work\pwidot\karlasal\102169744\d87	bb02-shr-plan.dgn	DRAWN -	REVISED -			785	(132-2,3,4, 133-1)RS	MADISON	122	30	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 76B80					
	PLOT DATE = 3/17/2011	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					