

COMBINATION CONCRETE CURB AND GUTTER, TYPE M6.24

LOCATION/DESCRIPTION	CCC&G TYPE M6.24 (FT)
EVERGREEN AVE. TO JACKSON ST. (MEDIAN)	425
EAST OF JACKSON ST. (MEDIAN)	225
EAST OF RR STRUCTURE (SN 060-0203)(MEDIAN)	500
BETWEEN FOSTERBURG ROAD AND GRASS MED. (MEDIAN)	650
AT POWDER MILL ROAD INTERSECTION (MEDIAN)	120
AT STANLEY ROAD INTERSECTION (MEDIAN)	125
WOODRIVER CREEK TO THELMA/FRANKLIN (MEDIAN)	425
TOTAL	2,470

PORTLAND CEMENT CONCRETE 10 INCH

LOCATION/DESCRIPTION	PCC PAVEMENT 10 IN (SQ YD)	PAVEMENT FABRIC (SQ YD)
AT POWDER MILL ROAD	510	510
AT STANLEY ROAD	845	845
TOTAL	1355	1355

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24

LOCATION/DESCRIPTION	COMBO C&G TYPE B-9.24 (FT)
BETWEEN RODGERS ST. AND HMA RAMPS (MEDIAN)	400
BETWEEN HMA RAMPS AND FOSTERBURG ROAD (MEDIAN)	1800
TOTAL	2,200

GUARDRAIL REMOVAL

LOCATION	GUARDRAIL REMOVAL (FT)
LOCATION 1	120
LOCATION 2	132
LOCATION 3	450
LOCATION 4A	728
LOCATION 4B	770
TOTAL	2,200

△ REVISED SHEET 4/13/11

FILE NAME =	USER NAME = karlesal	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
es:\pw\work\p\dot\karlesal\0169744\d87	bb00-ahp-plan.dgn	DRAWN - ---	REVISED - ---			785	(132-2,3,4, 133-1)RS	MADISON	122	37	
PLOT SCALE = 50.0000 ' / IN.	CHECKED - ---	REVISED - ---	REVISED - ---			CONTRACT NO. 76B80					
PLOT DATE = 3/18/2011	DATE - -----	REVISED - ---	REVISED - ---			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					
				SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____							