

PAVEMENT MARKING SCHEDULE

LOCATION	DESCRIPTION	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (SQ FT)	THERMOPLASTIC PAVEMENT MARKING - LINE 4"			THERMOPLASTIC PAVEMENT MARKING - LINE 12" (FOOT)	THERMOPLASTIC PAVEMENT MARKING - LINE 24" (FOOT)	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS (SQ FT)	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"		POLYUREA PAVEMENT MARKING TYPE I - LINE 6" (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)
			SOLID WHITE* (FOOT)	SOLID YELLOW (FOOT)	SKIP DASH YELLOW (FOOT)				SOLID YELLOW (FOOT)	SOLID WHITE (FOOT)			
STA 63+21 TO STA 63+41			40	80		11.8	14					2	
STA 63+50 TO STA 66+03		92.4	419	751.4		45.8	60				15	25	
STA 66+75 TO STA 74+60		124.8	1402	1860.4	258.5	60.2	24				42	56	
STA 74+60 TO STA 88+24		218.4		2728	682						68	66	
STA 88+24 TO STA 95+64							124.8	1456	364	155	36		
STA 101+75 TO STA 107+99	NO PASSING LT		1247	623	155.8						8	8	
STA 107+99 TO STA 112+90	SKIP DASH		896		122.8						6	6	
STA 119+90 TO STA 121+02	NO PASSING RT		1492	812	203						10	10	
STA 121+02 TO STA 123+09	SKIP DASH		414		51.8						3	3	
STA 123+09 TO STA 132+90	NO PASSING LT		1806	981	245.3						12	12	
STA 132+90 TO STA 153+29	SKIP DASH		4078		509.8						25	25	
STA 153+29 TO STA 162+57	NO PASSING RT		1714	928	232						12	12	
STA 162+57 TO STA 165+30	SKIP DASH		546		68.3						3	3	
STA 165+30 TO STA 173+04	NO PASSING LT		1548	774	193.5						10	10	
STA 173+04 TO STA 182+68	SKIP DASH		1746		241						13	13	
SUBTOTAL URBAN ST CLAIR COUNTY		435.6		29850		117.8	98	124.8	1820	155	263	251	
STA 182+68 TO STA 193+45	SKIP DASH		2154		269.3						13	13	
STA 193+45 TO STA 202+06	NO PASSING RT		1722	861	215.3						11	11	
STA 202+06 TO STA 204+80	SKIP DASH		548		68.5						3	3	
STA 204+80 TO STA 211+93	NO PASSING LT		1426	713	178.3						9	9	
STA 211+93 TO STA 213+45	DOUBLE - NO PASSING		304	304							2	2	
STA 213+45 TO STA 222+36	NO PASSING RT		1782	891	222.8						11	11	
STA 222+36 TO STA 223+73	DOUBLE - NO PASSING		214	274							2	2	
STA 223+73 TO STA 235+00	NO PASSING LT		2176	1127	281.8						14	14	
STA 235+00 TO STA 247+16	NO PASSING RT		2432	1216	304						15	15	
STA 247+16 TO STA 263+32	DOUBLE - NO PASSING		3157	3232							20	20	
STA 263+32 TO STA 272+97	NO PASSING LT		1930	965	241.3						12	12	
STA 272+97 TO STA 282+05	SKIP DASH		1816		227						11	11	
STA 282+05 TO STA 288+29	NO PASSING RT		1248	624	156						8	8	
SUBTOTAL RURAL ST CLAIR COUNTY		0		33280		0	0	0	0	0	131	131	
STA 288+29 TO STA 294+08	NO PASSING RT		1158	579	144.8						7	7	
STA 294+08 TO STA 300+72	DOUBLE - NO PASSING		1246	1328							8	8	
STA 300+72 TO STA 320+45	NO PASSING LT		3856	1973	493.3						25	25	
STA 320+45 TO STA 340+82	SKIP DASH		3988		509.3						25	25	
STA 340+82 TO STA 351+30	NO PASSING RT		2096	1048	262						13	13	
STA 351+30 TO STA 360+82	DOUBLE - NO PASSING		1848	1904							12	12	
STA 360+82 TO STA 372+07.5	NO PASSING LT		2251	1126	281.4						14	14	
STA 373+73.5 TO STA 385+00	SKIP DASH		2253		281.6						14	14	
STA 385+00 TO STA 391+75	NO PASSING RT		1350	675	168.8						8	8	
STA 391+75 TO STA 396+85	SKIP DASH		936		127.5						6	6	
STA 396+85 TO STA 403+04	NO PASSING LT		1238	619	154.8						8	8	
STA 403+04 TO STA 425+45	SKIP DASH		4391		560.3						28	28	
STA 425+45 TO STA 433+32	NO PASSING RT		1530	787	196.8						10	10	
STA 433+32 TO STA 435+89	SKIP DASH		514		64.3						3	3	
STA 435+89 TO STA 442+38	DOUBLE - NO PASSING		1298	1298							8	8	
STA 442+38 TO STA 443+45	NO PASSING LT		214	107	26.8						1	1	
STA 443+45 TO STA 450+28	NO PASSING RT		1366	683	170.8						9	9	
STA 450+28 TO STA 452+74	SKIP DASH		492		61.5						3	3	
STA 452+74 TO STA 458+21	NO PASSING LT		1094	547	136.8						7	7	
STA 458+21 TO STA 460+06.5	DOUBLE - NO PASSING		319	371							2	2	
SUBTOTAL MADISON COUNTY		0		50124		0	0	0	0	0	211	211	
SUBTOTAL		435.6	71695.0	32789.8	8768.9	117.8	98	124.8	1456.0	364.0	155	605	593
PAY TOTAL		436	113254			118	98	125	1820	155	605	593	

* INCLUDES OMISSIONS FOR SIDERoadS

FILE NAME =	USER NAME = betaj	DESIGNED - ESW	REVISED - 3-22-11	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S:\Projects\409-0028-SHY E. 4 Lebanon 3P\dgn\CADD	meta\087629-shy-echedule.dgn	DRAWN - PDB	REVISED -					314	(110, 111)RS-4	MADISON & ST CLAIR	58	9
PLOT SCALE = 48,0000' / IN.	CHECKED - BRM	REVISIED -						CONTRACT NO. 76E29				
PLOT DATE = 3/24/2011	DATE - 11-11-10	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
				SCALE:	SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.					