

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION	DESCRIPTION	SHORT-TERM PAVEMENT MARKING		TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS 1 APP (SQ FT)	TEMPORARY PAVEMENT MARKING - LINE 4"			TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
		YELLOW 4 APPS (FOOT)	WHITE 4 APPS (FOOT)		SOLID WHITE 1 APP (FOOT)	SOLID YELLOW 1 APP (FOOT)	SKIP DASH YELLOW 1 APP (FOOT)				
STATION TO STATION											
STA 63+21 TO STA 63+41		16			40	80			11.8	14	81.13
STA 63+50 TO STA 66+03		150.4	19.6	92.4	419	751.4			45.8	60	662.50
STA 66+75 TO STA 74+60		578.8	45.6	124.8	1402	1860.4	258.5		60.2	24	1458.67
STA 74+60 TO STA 88+24		1091.2		218.4	2728	682					1446.00
STA 88+24 TO STA 95+64				124.8	1456	364		155			808.97
STA 101+75.7 TO STA 107+99	NO PASSING LT	249.2			1247	623	155.8				696.03
STA 107+99 TO STA 112+90	SKIP DASH	196.4			896		122.8				355.97
STA 119+90 TO STA 121+02	NO PASSING RT	324.8			1492	812	203				862.73
STA 121+02 TO STA 123+09	SKIP DASH	82.8			414		51.8				162.17
STA 123+09 TO STA 132+90	NO PASSING LT	392.4			1806	981	245.3				1043.47
STA 132+90 TO STA 153+29	SKIP DASH	815.6			4078		509.8				1597.23
STA 153+29 TO STA 162+57	NO PASSING RT	371.2			1714	928	232				988.93
STA 162+57 TO STA 165+30	SKIP DASH	109.2			546		68.3				213.87
STA 165+30 TO STA 173+04	NO PASSING LT	309.6			1548	774	193.5				864.30
STA 173+04 TO STA 182+68	SKIP DASH	385.6			1746		241				694.47
SUBTOTAL URBAN ST CLAIR COUNTY		5139		560.4	31670			155	117.8	98	11937
STA 182+68 TO STA 193+45	SKIP DASH	430.8			2154		269.3				843.67
STA 193+45 TO STA 202+06	NO PASSING RT	344.4			1722	861	215.3				961.47
STA 202+06 TO STA 204+80	SKIP DASH	109.6			548		68.5				214.63
STA 204+80 TO STA 211+93	NO PASSING LT	285.2			1426	713	178.3				796.20
STA 211+93 TO STA 213+45	DOUBLE - NO PASSING	60.8			304	304					207.73
STA 213+45 TO STA 222+36	NO PASSING RT	356.4			1782	891	222.8				994.97
STA 222+36 TO STA 223+73	DOUBLE - NO PASSING	54.8			214	274					167.23
STA 223+73 TO STA 235+00	NO PASSING LT	450.8			2176	1127	281.8				1232.50
STA 235+00 TO STA 247+16	NO PASSING RT	486.4			2432	1216	304				1357.87
STA 247+16 TO STA 263+32	DOUBLE - NO PASSING	646.4			3157	3232					2183.53
STA 263+32 TO STA 272+97	NO PASSING LT	386.0			1930	965	241.3				1077.60
STA 272+97 TO STA 282+05	SKIP DASH	363.2			1816		227				711.27
STA 282+05 TO STA 288+29	NO PASSING RT	249.6			1248	624	156				696.80
SUBTOTAL RURAL ST CLAIR COUNTY		4224		0.0	33280.3			0	0	0	11446
STA 288+29 TO STA 294+08	NO PASSING RT	231.6			1158	579	144.8				646.57
STA 294+08 TO STA 300+72	DOUBLE - NO PASSING	265.6			1246	1328					880.13
STA 300+72 TO STA 320+45	NO PASSING LT	789.2			3856	1973	493.3				2173.20
STA 320+45 TO STA 340+82	SKIP DASH	814.8			3988		509.3				1567.00
STA 340+82 TO STA 351+30	NO PASSING RT	419.2			2096	1048	262				1170.27
STA 351+30 TO STA 360+82	DOUBLE - NO PASSING	380.8			1848	1904					1282.40
STA 360+82 TO STA 372+07.5	NO PASSING LT	450.4			2251	1126	281.4				1257.00
STA 373+73.5 TO STA 385+00	SKIP DASH	450.8			2253		281.6				882.43
STA 385+00 TO STA 391+75	NO PASSING RT	270.0			1350	675	168.8				753.77
STA 391+75 TO STA 396+85	SKIP DASH	204.0			936		127.5				371.50
STA 396+85 TO STA 403+04	NO PASSING LT	247.6			1238	619	154.8				691.23
STA 403+04 TO STA 425+45	SKIP DASH	896.4			4391		560.3				1725.13
STA 425+45 TO STA 433+32	NO PASSING RT	314.8			1530	787	196.8				864.17
STA 433+32 TO STA 435+89	SKIP DASH	102.8			514		64.3				201.33
STA 435+89 TO STA 442+38	DOUBLE - NO PASSING	259.6			1298	1298					886.97
STA 442+38 TO STA 443+45	NO PASSING LT	42.8			214	107	26.8				119.50
STA 443+45 TO STA 450+28	NO PASSING RT	273.2			1366	683	170.8				762.70
STA 450+28 TO STA 452+74	SKIP DASH	98.4			492		61.5				192.70
STA 452+74 TO STA 458+21	NO PASSING LT	218.8			1094	547	136.8				610.83
STA 458+21 TO STA 460+06.5	DOUBLE - NO PASSING	74.4			319	371					236.20
SUBTOTAL MADISON COUNTY		6805		0.0	50124			0	0.0	0.0	17275
SUBTOTAL		16102.8	65.2	560.4	73151.0	32789.8	9132.9	155	117.8	98	40658
PAY TOTAL		16168		561	115074			155	118	98	40658

* INCLUDES OMISSIONS FOR SIDEROADS

PAVEMENT PATCHING SCHEDULE

NORTHBOUND						
LOCATION	APPROX. STATION	LENGTH (FT)	WIDTH (FT)	PAVEMENT PATCHING 14"		
				TYPE II (SQ YD)	TYPE III (SQ YD)	TYPE IV (SQ YD)
0	63+21	10	12	13.33		
0.8	105+45	10	12	13.33		
1	116+01	6	20	13.33		
1.3	131+85	6	20	13.33		
1.5	142+41	12	12		16	
2.3	182+68	MIDGLEY NEISS RD				
2.5	195+21	6	12	8		
3.15	227+69	EMERALD MOUND RD				
3.9	269+13	6	12	8		
4.5	300+81	12	12		16	
4.6	306+09	12	12		16	
4.7	311+37	12	12		16	
4.8	313+90	ROSE RD				
4.95	324+57	6	12	8		
5.1	332+49	12	12		16	
5.2	337+77	12	12		16	
5.35	340+39	LEBANON RD				
5.55	353+72	PANSY RD				
5.6	358+89	12	12		16	
5.75	366+81	12	12		16	
6.2	390+57	12	12		16	
6.35	394+15	LILAC RD				
6.65	414+33	12	12		16	
6.7	416+97	12	12		16	
6.8	420+51	KIRSCH RD				
6.95	430+17	12	20			26.67
7.2	443+37	12	12		16	
7.4	453+93	12	12		16	
7.45	456+57	12	12		16	
7.6	464+49	END SECTION				
NORTHBOUND TOTALS				63.99	224	26.67
SOUTHBOUND						
LOCATION	APPROX. STATION	LENGTH (FT)	WIDTH (FT)	PAVEMENT PATCHING 14"		
				TYPE II (SQ YD)	TYPE III (SQ YD)	TYPE IV (SQ YD)
0	63+21	10	12	13.33		
0.9	110+73	10	12	13.33		
1	116+01	6	20	13.33		
1	116+01	6	20	13.33		
1.1	121+29	6	20	13.33		
1.1	121+29	12	20			26.67
1.3	131+85	6	20	13.33		
1.5	142+41	6	20	13.33		
1.55	145+05	6	20	13.33		
2.1	174+09	6	12	8		
2.3	184+65	6	12	8		
2.3	182+68	MIDGLEY NEISS RD				
2.55	197+85	6	12	8		
2.9	216+33	6	6	4		
3.1	226+89	12	12		16	
3.15	227+69	EMERALD MOUND RD				
3.9	269+13	6	12	8		
4.5	300+81	12	12		16	
4.6	306+09	12	12		16	
4.7	311+37	12	12		16	
4.8	313+90	ROSE RD				
4.95	324+57	6	12	8		
5.1	332+49	12	12		16	26.67
5.2	337+77	12	12		16	
5.3	343+05	6	20	13.33		
5.35	340+39	LEBANON RD				
5.4	348+33	6	20	13.33		
5.55	353+72	PANSY RD				
5.65	361+53	12	12		16	
5.75	366+81	12	12		16	
6.2	390+57	6	12	8		
6.35	394+15	LILAC RD				
6.4	401+13	12	12		16	
6.65	414+33	6	30		20	
6.7	416+97	12	25			33.33
6.8	420+51	KIRSCH RD				
6.9	427+53	6	30		20	
6.9	427+53	6	20	13.33		
6.95	430+17	12	20			26.67
7.2	443+37	12	12		16	
7.3	448+65	6	12	8		
7.4	453+93	12	12		16	
7.45	456+57	12	12		16	
7.6	464+49	END SECTION				
SOUTHBOUND TOTALS				207	216	113.34
SUBTOTAL				270.99	440	140
15% FOR ANTICIPATED FAILURES				40.6	66	21
TOTAL				311.59	506.00	161
PAY TOTAL				312	506	161
SPLIT URBAN ST CLAIR COUNTY				187	19	31
SPLIT RURAL ST CLAIR COUNTY				42	18	0
SPLIT MADISON COUNTY				83	469	130

FILE NAME =
S:\Projects\409-0028-811 IL 4 Lebanon 3P\dgn\CADD

USER NAME = betay
DESIGNED - ESW
DRAWN - PDB
CHECKED - BRM
DATE - 11-11-