

INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS, GENERAL NOTES, HIGHWAY STANDARDS
3. LOCATION MAP OF STRUCTURES
4. SUMMARY OF QUANTITIES
5. EARTHWORK ANALYSIS
6. SCHEDULE OF QUANTITIES
7. DETAILS OF CRASHWALL EXTENSION MEDIAN PIER S.N. 061-0017
8. DETAILS OF CRASHWALL EXTENSION MEDIAN PIER S.N. 061-0010
9. CONCRETE COLLAR
10. IMPACT ATTENUATORS (NON-REDIRECTIVE) TEST LEVEL 3
11. INLET BOXES TO BE ADJUSTED (SPECIAL)
12. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0027
13. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0046
14. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0017
15. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0045
16. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0028
17. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0044
18. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0026
19. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0042
20. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0043
21. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0025
22. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0057
23. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0010
24. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0058
25. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0061
26. PLAN AND PROFILE OF IMPACT ATTENUATORS AT S.N. 061-0064
- 27-30. CROSS SECTIONS AT S.N. 061-0027
- 31-34. CROSS SECTIONS AT S.N. 061-0046
- 35-38. CROSS SECTIONS AT S.N. 061-0017
- 39-42. CROSS SECTIONS AT S.N. 061-0045
- 43-46. CROSS SECTIONS AT S.N. 061-0028
- 47-50. CROSS SECTIONS AT S.N. 061-0044
- 51-54. CROSS SECTIONS AT S.N. 061-0026
- 55-58. CROSS SECTIONS AT S.N. 061-0042
- 59-62. CROSS SECTIONS AT S.N. 061-0043
- 63-66. CROSS SECTIONS AT S.N. 061-0025
- 67-70. CROSS SECTIONS AT S.N. 061-0057
- 71-74. CROSS SECTIONS AT S.N. 061-0010
- 75-78. CROSS SECTIONS AT S.N. 061-0058
- 79-82. CROSS SECTIONS AT S.N. 061-0061
- 83-86. CROSS SECTIONS AT S.N. 061-0064

HIGHWAY STANDARDS

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-02 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 280001-05 TEMPORARY EROSION CONTROL SYSTEMS
- 542301-03 PRECAST REINFORCED CONCRETE FLARED END SECTION
- 542311-02 GRATING FOR CONCRETE FLARED END SECTION
- 542511-02 INLET BOX TYPE 24 C
- 542521-02 INLET BOX TYPE 24 E
- 542546-01 FLUSH INLET BOX FOR MEDIAN
- 601001-04 SUB-SURFACE DRAINS
- 601101-01 CONCRETE HEADWALL FOR PIPE DRAIN
- 602406-04 MANHOLE TYPE A 6' DIAMETER
- 604001-03 FRAME AND LIDS TYPE 1
- 701101-02 OFF-RD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
- 701400-05 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701406-06 LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
- 701901-01 TRAFFIC CONTROL DEVICES

GENERAL NOTES

1. EXISTING PIPE UNDERDRAIN OUTLETS AND DRAINAGE STRUCTURES IN THE MEDIAN SLOPES SHALL BE PRESERVED AND PROTECTED DURING CONSTRUCTION. ANY DAMAGE TO AN UNDERDRAIN OUTLET RESULTING FROM CONSTRUCTION ACTIVITY SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
2. IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16 THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 107.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
3. ONE APPLICATION OF TEMPORARY EROSION CONTROL SEEDING HAS BEEN INCLUDED. THE ACTUAL QUANTITY, LOCATIONS AND APPLICATIONS SHALL BE AS DIRECTED BY THE ENGINEER. THE APPLICATION RATE SHALL BE AS PER ARTICLE 280.04(f).
4. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST 14 DAYS IN ADVANCE OF STARTING ANY CONSTRUCTION WORK". THIS ADDITIONAL INFORMATION IS REQUIRED SO THAT THE PUBLIC CAN BE NOTIFIED OF THE PENDING CONSTRUCTION.
5. EXISTING PIPE UNDERDRAINS AFFECTED BY CONSTRUCTION SHALL BE ADJUSTED, EXTENDED AND/OR INCORPORATED INTO THE PIPE CULVERTS TO PROVIDE DRAINAGE AS DIRECTED BY THE ENGINEER. PIPE UNDERDRAIN HEADWALLS MAY NEED TO BE REMOVED AND RELOCATED. THE COST OF THIS WORK SHALL BE INCLUDED IN THE PRICE FOR IMPACT ATTENUATORS.
6. INFORMATION ON THE PLANS REGARDING UNDERGROUND UTILITIES IS TAKEN FROM THE BEST AVAILABLE RECORDS, BUT IS NOT REPRESENTED AS BEING ENTIRELY CORRECT OR COMPLETE. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IN ADVANCE OF CROSSING OVER OR UNDER ANY UTILITIES SHOWN ON THE PLANS AND SHALL NOTIFY IMMEDIATELY UPON DISCOVERY OF ANY UTILITY NOT SHOWN ON THE PLANS.
7. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF UTILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

- AMEREN ILLINOIS (GAS & ELECTRIC)
- ATMOS ENERGY CORPORATION (GAS)
- AT&T ILLINOIS (COMMUNICATIONS)
- CENTERPOINT ENERGY (PIPELINE)
- CHARTER COMMUNICATIONS, INC. (CABLE TV)
- CITY OF KINMUNDY (WATER & SANITARY SEWER)
- CITY OF SALEM (GAS, WATER, & SANITARY SEWER)
- COUNTRYMARK COOPERATIVE, LLP (PIPELINE)
- FMC WATER COMPANY (WATER)
- FRONTIER NORTH, INC. (COMMUNICATIONS)
- MARATHON PETROLEUM COMPANY, LLC (PIPELINE)
- NORTHEAST MARION COUNTY WATER COMPANY (WATER)
- PAETEC (COMMUNICATIONS)
- RACCOON WATER COMPANY (WATER)
- SOUTHWESTERN ELECTRIC COOPERATIVE, INC. (ELECTRIC)
- TRI-COUNTY ELECTRIC COOPERATIVE, INC. (ELECTRIC)
- US SONET, LLC (COMMUNICATIONS)
- VILLAGE OF ODIN (WATER & SANITARY SEWER)
- WOOD RIVER BP AMOCO PIPELINE (PIPELINE)

MEMBERS OF J.U.L.I.E. (800-892-0123) ARE INDICATED BY AN *.
NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY

COMMITMENTS

NONE

▲ REVISED SHEET 4/12/11

FILE NAME =	USER NAME = keplerc1	DESIGNED - K.M.M.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES, HIGHWAY STANDARDS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cs:\pw_work\wdot\keplerc1\0263834\087	E30-shr\enote-02.dgn	CHECKED - L.D.G.	REVISED -			57	61-(1,2,3,4,5,6)-I	MARION	86	2	
	PLOT SCALE = 1.000' / 1 IN.	DRAWN - K.H.L.	REVISED -			CONTRACT NO. 76E30					
	PLOT DATE = 3/16/2011	CHECKED - B.G.H.	REVISED -			ILLINOIS FED. AID PROJECT					