

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0021 90% FED 10% STATE	---	---	CODE NO	ITEM	UNIT		---	---	---
20200500	EARTH EXCAVATION (WIDENING)	CU YD	695.7	695.7									
25000210	SEEDING, CLASS 2A	ACRE	1.61	1.61									
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	145.5	145.5									
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	145.5	145.5									
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	145.5	145.5									
25100115	MULCH, METHOD 2	ACRE	1.61	1.61									
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	161	161									
28000400	PERIMETER EROSION BARRIER	FOOT	200	200									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2933.3	2933.3									
64200105	SHOULDER RUMBLE STRIPS	FOOT	8800	8800									
67100100	MOBILIZATION	L SUM	1	1									
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1									
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15									
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1									

FILE NAME =	USER NAME = *USER*	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	F.A.P. RTE. _____	SECTION _____	COUNTY _____	TOTAL SHEETS _____	SHEET NO. _____
#FILE#		DRAWN - ---	REVISED - ---					.793	112-1	BOND	8	3
		CHECKED - ---	REVISED - ---									
		DATE - ---	REVISED - ---									

CONTRACT NO. 76E32

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT