

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	0005			SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	0005		
CODE NO	ITEM	UNIT		MARION CO.		CLINTON CO.	CODE NO	ITEM	UNIT		MARION CO.		CLINTON CO.
				80% FED. 20% STATE	50% STATE 50% CITY	80% FED. 20% STATE					80% FED. 20% STATE	50% STATE 50% CITY	80% FED. 20% STATE
31200100	STABILIZED SUBBASE 4"	SO YD	2266	2266		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	278	278			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18.5	18.3	0.2	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	736	736			
40600300	AGGREGATE (PRIME COAT)	TON	89	87	2	* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6074	6074			
40600990	TEMPORARY RAMP	SO YD	1604	1604		* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1241	1241			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2599	2567	32	* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	278	278			
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	2266	2266		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	205	205			
42001300	PROTECTIVE COAT	SO YD	2266	2266		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	205	205			
44000100	PAVEMENT REMOVAL	SO YD	2266	2266		80300100	LOCATING UNDERGROUND CABLE	FOOT	20	20			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	3948	3948		88600600	DETECTOR LOOP REPLACEMENT	FOOT	1140	1140			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	26127	25934	193	X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1079	1063	16		
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	163	163									
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	106	106									
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SO YD	631	631									
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	229	229									
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	207	207									
44201299	DOWEL BARS 1 1/2"	EACH	812	812									
44213200	SAW CUTS	FOOT	5527	5527									
44213204	TIE BARS 3/4"	EACH	76	76									
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3476	3476									
45100100	CRACK ROUTING (PAVEMENT)	FOOT	8551	8075	476								
45100200	CRACK FILLING	POUND	2882	2725	157								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5									
67100100	MOBILIZATION	L SUM	1	1									
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.5	0.5								
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1									
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.5	0.5								
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1									
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5									
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2209	2209									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6074	6074									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1241	1241									

*SPECIALTY
ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - ---	REVISED - ---			805	(72-2, 82-2)RS-1	*	21	3	
	PLOT SCALE = #SCALE#	CHECKED - ---	REVISED - ---			CONTRACT NO. 76E51					
	PLOT DATE = #DATE#	DATE - ---	REVISED - ---			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____ *CLINTON/MARION