

GENERAL NOTES

COMMITMENTS

1. THE STANDARDS AND REVISIONS LISTED APPLY TO THIS PROJECT.
2. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

UTILITIES FROM CURVED STRUCTURE OVER IL 255

- AMEREN UE
- SBC
- FOSTERBURG WATER
- ILLINOIS AMERICAN WATER - ALTON
- MCI WORLDCOM
- AT&T CABLE SERVICES
- SPRINT
- VILLAGE OF GODFREY
- CHARTER COMMUNICATIONS

UTILITIES FROM THE STRUCTURE OVER HUMBERT ROAD

- AMEREN UE
- AMERITECH
- FOSTERBURG WATER
- ILLINOIS AMERICAN WATER - ALTON
- MCI WORLDCOM
- AT&T CABLE SERVICES
- SPRINT
- CHARTER COMMUNICATIONS

UTILITIES FROM THE STRUCTURE OVER IL 111

- AMEREN UE
- SBC
- AMERITECH
- FOSTERBURG WATER
- ILLINOIS AMERICAN WATER - ALTON
- MCI WORLDCOM
- AT&T CABLE SERVICES
- SPRINT
- VILLAGE OF GODFREY
- CHARTER COMMUNICATIONS


MEMBERS OF J.U.L.I.E. CALL TOLL FREE (800) 892-0123 OR 811 AND ARE INDICATED BY A "•". NON-JULIE MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

3. THE RESIDENT ENGINEER SHALL VERIFY THE EXISTENCE OF HIGHWAY LIGHTING AND/OR I.T.S. UTILITIES WITHIN THE PROJECT LIMITS. IF HIGHWAY LIGHTING AND/OR I.T.S. EXISTS WITHIN THE PROJECT LIMITS, AND IF THESE ITEMS REQUIRE LOCATING, THE CONTRACTOR SHALL BE DIRECTED TO DO SO ACCORDING TO SECTION 803 OF THE STANDARD SPECIFICATIONS. THIS WORK SHALL BE PAID FOR ACCORDING TO ARTICLE 803.04 OF THE STANDARD SPECIFICATIONS. THESE PLANS WERE PREPARED USING ENGLISH UNITS. HOWEVER, IT SHOULD BE NOTED THAT THE CENTERLINE STATIONING USES METRIC UNITS FROM THE ORIGINAL ROADWAY CONSTRUCTION PLANS.
4. EXISTING UNDERGROUND AND ABOVE-GRADE FACILITIES, STRUCTURES, AND UTILITIES HAVE BEEN PLOTTED ON THESE CONTRACT DOCUMENTS BASED UPON THE INFORMATION AND SURVEYS AVAILABLE AT THE TIME OF DRAWING PREPARATION. THE LOCATION OF THESE FEATURES MUST, THEREFORE, BE CONSIDERED APPROXIMATE ONLY. IN ADDITION, THERE MAY BE OTHER FACILITIES, STRUCTURES, AND UTILITIES WHICH DID NOT EXIST (OR THE EXISTENCE OF WHICH WAS NOT KNOWN) AT THE TIME OF DRAWING PREPARATION. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR(S) TO HAVE ALL EXISTING FACILITIES, STRUCTURES, AND UTILITIES LOCATED IN THE FIELD PRIOR TO ANY EXCAVATION OR CONSTRUCTION ACTIVITY; AND TO PROTECT ALL SUCH EXISTING FEATURES (EXCEPT THOSE SPECIFICALLY NOTED FOR REMOVAL OR DEMOLITION) DURING CONSTRUCTION.
5. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT INTERCHANGES, ENTRANCES AND SIDE STREETS WHERE WORK IS BEING CONDUCTED AS DIRECTED BY THE RESIDENT ENGINEER. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE. THIS SHALL BE INCLUDED IN THE COST OF THE TRAFFIC CONTROL AND PROTECTION. THESE SIGNS SHALL BE 48" X 48".
6. SEEDING, FERTILIZER AND MULCH REQUIRED AROUND THE PROPOSED WORK SHALL BE INCIDENTAL TO THE CONTRACT.

7. IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16, THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 107.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
8. SHOULDER WIDENING FOR THE TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT SHALL BE INCLUDED IN THE UNIT PRICE OF THE TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT AND CONSTRUCTED ACCORDING TO STANDARD 630301.
9. ALL TYPE III BARRICADES SHALL REQUIRE AN ADEQUATE NUMBER OF SANDBAGS PER BARRICADE TO ENSURE STABILIZATION.

NONE

**** METRIC STATIONING ****
ALL OTHER OFFSETS, DIMENSIONS & VALUES USE ENGLISH UNITS

FILE NAME = ...\\0876E76-Sht-GenNote.dgn	USER NAME = CFC...	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		GENERAL NOTES & COMMITMENTS		F.A.P. RTE. 310	SECTION 60-155G	COUNTY MADISON	TOTAL SHEETS 54	SHEET NO. 2
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 76E76									
PLOT DATE = 2/1/2011	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									
			SCALE: NONE					SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		