

PREFORMED PLASTIC PAVEMENT MARKING SCHEDULE (SHEET 2)

LOCATION STATION TO STATION	PRE. PLASTIC PVMT. MARK. TYPE B - INLAID - LINE 4"				PRE. PLASTIC PVMT. MARK. TYPE B - INLAID - LINE 12"		PRE. PLASTIC PVMT. MARK. TYPE B - INLAID - LINE 24"	PRE. PLASTIC PVMT. MARK. TYPE B - INLAID - LETTERS AND SYMBOLS	REMARKS
	WHITE SOLID FOOT	YELLOW SOLID FOOT	WHITE DASHED FOOT	YELLOW DASHED FOOT	WHITE SOLID FOOT	YELLOW SOLID FOOT	FOOT	SQ FT	
IL 148									
53+20								23.6	2 "ONLY"
53+80								31.2	2 LT ARROWS
53+84								11.8	"ONLY"
54+44								15.6	RT ARROW
55+18								23.6	2 "ONLY"
55+78								31.2	2 LT ARROWS
56+08							24		STOPBAR
56+39							24		STOPBAR
57 + 67.00 RT TO 58 + 97.00 RT									
57 + 67.00 RT TO 64 + 79.00 RT			178						
57+83							24		STOPBAR
57 + 83.00 LT TO 58 + 97.00 LT									SKP DASHES
57 + 83.00 LT TO 58 + 97.00 LT									LT TURN LANE
57 + 83.00 LT TO 61 + 70.00 LT	387								LT TURN LANE
57 + 83.00 LT TO 64 + 79.00 LT			174						
58+15							24		STOPBAR
58 + 15.00 TO 58 + 97.00									LT TURN LANE
58 + 15.00 TO 58 + 97.00									DOUBLE CENTERLINE
58 + 15.00 TO 59 + 88.00		346							DOUBLE CENTERLINE
58 + 15.00 LT TO 61 + 70.00 LT	355								LT TURN LANE
58 + 78.00 LT TO 59 + 65.50 LT									
58 + 78.00 LT TO 60 + 43.50 LT	166								RT TURN LANE
58 + 81.00 RT TO 58 + 97.00 RT									RT OUTSIDE EDGE LINE
58 + 97.00 RT TO 64 + 79.00 RT	582								RT OUTSIDE EDGE LINE
59+00								31.2	2 LT ARROWS
59 + 18.00 LT TO 64 + 79.00 LT	561								LT OUTSIDE EDGE LINE
59 + 18.00 LT TO 59 + 65.50 LT									
59+60								23.6	2 "ONLY"
59+83 LT								15.6	RT ARROW
59 + 88.00 TO 64 + 79.00		1980				120			PAINTED MEDIAN
60+43 LT								11.8	"ONLY"
61+02								31.2	2 LT ARROWS
61+62								23.6	2 "ONLY"
62+68 RT								11.8	"ONLY"
63+28 RT								15.6	LT ARROW
63+84 RT								11.8	"ONLY"
64+44 RT								15.6	LT ARROW
SUB TOTALS	2051	2326	352	0	0	120	96	328.8	
SHEET 2 TOTALS			4729			120	96	328.8	
TOTALS FROM SHEET 1 & SHEET 2			20816			1060	252	657.6	