

SUMMARY OF QUANTITIES			
CODE #	ITEM	UNIT	HBP FUNDING 80% FEDERAL 20% STATE SN 097-0075 00II
20200100	EARTH EXCAVATION	CU YD	156
20300100	CHANNEL EXCAVATION	CU YD	470
20400800	FURNISHED EXCAVATION	CU YD	605
*25000210	SEEDING, CLASS 2A	ACRE	0.55
*25000350	SEEDING, CLASS 7	ACRE	0.55
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	50
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	50
*25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.10
*25100115	MULCH, METHOD 2	ACRE	1.10
*25100630	EROSION CONTROL BLANKET	SQ YD	2559
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	220
28000305	TEMPORARY DITCH CHECKS	FOOT	22
28000400	PERIMETER EROSION BARRIER	FOOT	1422
28100107	STONE RIPRAP, CLASS A4	SQ YD	807
28200200	FILTER FABRIC	SQ YD	807
35600719	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 3/4"	SQ YD	144
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	180
40600300	AGGREGATE (PRIME COAT)	TON	4
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	131
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174
40600990	TEMPORARY RAMP	SQ YD	234
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	191
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	166
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	44
44000100	PAVEMENT REMOVAL	SQ YD	380
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	144
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	428
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	250
50300100	FLOOR DRAINS	EACH	8
50300225	CONCRETE STRUCTURES	CU YD	172.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	255.6
50300260	BRIDGE DECK GROOVING	SQ YD	592
50300280	CONCRETE ENCASEMENT	CU YD	14.8
50300300	PROTECTIVE COAT	SQ YD	772
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	2232
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	76920

SUMMARY OF QUANTITIES			
CODE #	ITEM	UNIT	HBP FUNDING 80% FEDERAL 20% STATE SN 097-0075 00II
50800515	BAR SPLICERS	EACH	770
51201800	FURNISHING STEEL PILES HP14X73	FOOT	720
51201900	FURNISHING STEEL PILES HP14X89	FOOT	1064
51202305	DRIVING PILES	FOOT	1784
51203800	TEST PILE STEEL HP14X73	EACH	2
51203900	TEST PILE STEEL HP14X89	EACH	1
51204650	PILE SHOES	EACH	28
51500100	NAME PLATES	EACH	1
52100505	ANCHOR BOLTS, 5/8"	EACH	24
52100520	ANCHOR BOLTS, 1"	EACH	24
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	52
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	500
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	856
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	8
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	222
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1834
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	678
70400100	TEMPORARY CONCRETE BARRIER	FOOT	450
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	425
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1834
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	14
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	318
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	11
*86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1

SUMMARY OF QUANTITIES			
CODE #	ITEM	UNIT	HBP FUNDING 80% FEDERAL 20% STATE SN 097-0075 00II
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	83.5
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1
X5080600	MECHANICAL SPLICERS	EACH	72
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22
Z0022800	FENCE REMOVAL	FOOT	125
Z0026407	TEMPORARY SHEET PILING	SQ FT	895
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	130

* SPECIALTY ITEM