

ROADWAY SCHEDULE												
LOCATION	HOT-MIX ASPHALT BASE COURSE WIDENING 10 3/4"	BITUMINOUS MATERIAL PRIME COAT	AGGREGATE PRIME COAT	LEVELING BINDER (MACHINE METHOD) N90	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	HOT-MIX ASPHALT BINDER COURSE IL-19.0, N90	HOT-MIX ASPHALT SURFACE COURSE MIX C, N90	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	PAVEMENT REMOVAL	AGGREGATE SHOULDERS TYPE A	HOT-MIX ASPHALT SHOULDERS
	35600719	40600100	40600300	40600645	40600982	40600990	40603090	40603320	42001420	44000100	48100500	48203029
	SQ YD	GAL	TON	TON	SQ YD	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD
F.A.P. ROUTE 28 (US 45)												
STAGE I												
RT. STA 806+35 TO RT. STA 810+40	76									36		
LT. STA 806+35 TO RT. STA 810+40	68					75			22	198		211
STAGE II												
RT. STA 804+82.88 TO RT. STA 810+94.63						75			22	146		217
CL STA 804+55 TO CL STA 807+44		83	2	37	87	42	123	76			56	
CL STA 809+33.50 TO CL STA 812+70		97	2	94	87	42	68	90			88	
TOTAL	144	180	4	131	174	234	191	166	44	380	144	428

FENCE REMOVAL SCHEDULE	
LOCATION	FENCE REMOVAL Z0022800 FOOT
FAP 328 US 45	
LT. STA 809+25 TO LT. STA 810+50	125
TOTAL	125

SEEDING SCHEDULE								
LOCATION	SEEDING CLASS 2A	SEEDING CLASS 7	TEMPORARY EROSION CONTROL SEEDING *	NITROGEN FERTILIZER NUTRIENT**	PHOSPHORUS FERTILIZER NUTRIENT 90 LBS/ACRE	POTASSIUM FERTILIZER NUTRIENT 90 LBS/ACRE	AGRICULTURAL GROUND LIMESTONE 2 TONS/ACRE	MULCH METHOD 2
	25000210	25000350	28000250	25000400	25000500	25000600	25000700	25100115
	ACRE	ACRE	LBS	LBS	LBS	LBS	TONS	ACRE
FAP 328 US 45								
STAGE I								
LT STA 804+55 TO LT 808+15	0.10	0.10	40	13	9	9	0.20	0.20
LT STA 808+80 TO LT 812+70	0.13	0.13	52	17	12	12	0.26	0.26
STAGE II								
RT STA 804+55 TO RT 808+15	0.19	0.19	76	25	17	17	0.38	0.38
RT STA 808+80 TO RT 812+70	0.13	0.13	52	17	12	12	0.26	0.26
TOTAL	0.55	0.55	220	72	50	50	1.10	1.10

* 100 LBS/ACRE FOR 4 APPLICATIONS

** 90 LBS/ACRE FOR SEEDING CLASS 2A AND 40 LBS/ACRE FOR SEEDING CLASS 7

GUARDRAIL SCHEDULE						
LOCATION	STEEL PLATE BEAM GUARD RAIL TYPE A 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	GUARDRAIL REMOVAL	GUARDRAIL MARKERS TYPE A	TERMINAL MARKER DIRECT APPLIED
	63000001	63100085	63100167	63200310	78200410	78201000
	FOOT	EACH	EACH	FOOT	EACH	EACH
FAP 328 US 45						
STAGE I						
LT. STA 805+96.85 TO LT. STA 811+80.65	250	2	2	427	7	2
STAGE II						
RT. STA 804+96.85 TO RT. STA 810+80.65	250	2	2	429	7	2
TOTAL	500	4	4	856	14	4

FILE NAME = 0920116-sht-schedule1.dgn

USER NAME =

DESIGNED - L.F.S.

REVISED -

DRAWN - T.W.K.

CHECKED - J.W.F.

REVISED -

PLOT SCALE =

DATE - 09/14/10

REVISED -

PLOT DATE = 1/5/2011

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



SCHEDULE OF QUANTITIES
U.S. ROUTE 45

SCALE:

SHEET NO. OF SHEETS STA. TO STA.

F.A.P.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	105B-2	WHITE	55	7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 78188	