

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SIGNATURE BLOCK
3	INDEX OF SHEETS; HIGHWAY STANDARDS; STRUCTURE RATINGS; GENERAL NOTES
4 - 5	TYPICAL SECTIONS
6	SUMMARY OF QUANTITIES
7	RESURFACING SCHEDULE
8	THERMOPLASTIC PAVEMENT MARKING SCHEDULE
9	LOCATION MAP - FAP 331 (IL. 13) EASTBOUND LANES NEAR WILLIAMSON/SALINE COUNTY LINE
10 - 17	PLAN SHEETS
18 - 21	PAVEMENT MARKING DETAIL SHEETS

HIGHWAY STANDARDS

701421-03
 701426-04
 701901-01
 780001-02
 781001-03

GENERAL NOTES

THE AGGREGATE TO BE USED IN THE MICRO-SURFACING SHALL BE TYPE II APPLIED AT 16 LB/SQ YD PER PASS.

BITUMINOUS MATERIAL (PRIME COAT) SHALL BE APPLIED PRIOR TO PLACING THE FIRST PASS OF MICRO-SURFACING AT A RATE OF 0.05 - 0.10 GAL/SQ. YD.

THE QUANTITY OF SHORT TERM PAVEMENT MARKING SHOWN IN THE PLANS WAS BASED ON ONE APPLICATION EACH FOR 1 LAYER OF THE PRIME COAT AND 1 LAYER OF SURFACE TREATMENT.

PRIOR TO PLACEMENT OF THE FINAL PAVEMENT MARKINGS THE RESIDENT ENGINEER SHOULD CONTACT THE BUREAU OF OPERATIONS AND ARRANGE FOR INSPECTION AND APPROVAL OF THE PAVEMENT MARKING LAYOUT.

THE CONTRACTOR SHALL PRESERVE EXISTING STAMPED STATIONING.

THE CONTRACTOR SHOULD FOLLOW THE EXISTING HOT-MIX LAYOUT AS CLOSELY AS POSSIBLE. EACH INDIVIDUAL LANE SHOULD BE DONE EDGE TO EDGE IN ONE PASS. SHOULDERS SHALL BE DONE SEPARATELY.

THE FRICTION AGGREGATE SHALL BE MIXTURE D.

STRUCTURE RATINGS

STRUCTURE NO.	INV. RATING	OPER. RATING	SUFF. RATING
FAI 331 (IL. 13) WESTBOUND LANES - WILLIAMSON COUNTY			
100-2011	20.0	27.2	78.3
FAI 331 (IL. 13) WESTBOUND LANES - SALINE COUNTY			
083-2011	37.6	55.0	84.5
083-0051	24.0	40.2	99.8
083-7036	NA	NA	84.5
083-7037	NA	NA	83.4
083-7038	NA	NA	85.0
083-7039	NA	NA	81.0
083-7040	NA	NA	83.4

*WILLIAMSON/SALINE COUNTIES

FILE NAME *	USER NAME * mcoordkr	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES AND STRUCTURE INFORMATION	F.A.P. RTE. *	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
os\pwwork\pwwork\mcoordkr\d0209826\7818-shr-plan.dgn		DRAWN - ---	REVISED - ---			331	09_PAVI_PRES_EX11-1		21	3	
PLOT SCALE = 100.0000' / IN.		CHECKED - ---	REVISED - ---			CONTRACT NO. 70219					
PLOT DATE = 1/24/2011		DATE - ---	REVISED - ---			ILLINOIS FED. AID PROJECT					