

HOT-MIX ASPHALT PAVEMENT

LOCATION STATION TO STATION	HOT-MIX ASPHALT BINDER COURSE IL-19.0, N90	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE MIX "D", N90	AGGREGATE (PRIME COAT)
	TON	GALLON	TON	TON
IL 13 (EB)				
STA 1803+52 TO STA 1807+50	743	744	105	6
STA 1818+00 TO STA 1822+50	839	841	118	6
IL 13 (WB)				
STA 1802+97 TO STA 1807+50	846	847	119	6
STA 1818+50 TO STA 1822+06.50	665	666	94	5
IL 13 (MEDIAN REMOVAL LOCATION)				
STA 1804+23 TO STA 1805+61	55	55	8	0.5
STA 1819+86 TO STA 1821+24	21	21	3	0.2
TEMPORARY RAMP A				
STA 11+33.78 TO STA 13+94.97	529	529	74	4
TEMPORARY RAMP B				
STA 20+26.16 TO STA 21+80.91	393	393	55	3
TEMPORARY RAMP C				
STA 7+49.25 TO STA 9+99.81	455	455	63	3
TEMPORARY RAMP D				
STA 126+66.22 TO STA 127+82.04	110	97	4	0.9
STA 127+54 TO STA 128+45	42	13	12	0.5
STA 128+45 TO STA 129+09.24	29	41	15	0.2
TOTAL FROM SHOULDER SCHEDULE		469		
PROJECT TOTAL	4727	5171	670	35

SHOULDERS

LOCATION STATION TO STATION	HOT-MIX ASPHALT SHOULDERS	HOT-MIX ASPHALT SHOULDERS 8"	AGGREGATE SHOULDERS, TYPE A 8"	BITUMINOUS MATERIALS (PRIME COAT)*
	TON	SQ YD	SQ YD	GALLON
IL 13 (EB)				
STA 1804+69 TO STA 1807+50			173	
STA 1818+00 TO STA 1820+74			61	
IL 13 (WB)				
STA 1804+72 TO STA 1807+50			62	
STA 1818+50 TO STA 1820+74			50	
TEMPORARY RAMP A				
STA 11+33.78 TO STA 13+94.97		320		131
TEMPORARY RAMP B				
STA 20+26.16 TO STA 21+80.91		234		96
TEMPORARY RAMP C				
STA 7+49.25 TO STA 9+99.81		305		125
TEMPORARY RAMP D				
STA 127+46.83 TO STA 128+45	21			10
STA 126+66.22 TO STA 129+13.34		194		80
STA 127+54 TO STA 128+45				27
PROJECT TOTAL	21	1053	346	469

* SEE HOT-MIX ASPHALT PAVEMENT SCHEDULE FOR ADDITIONAL QUANTITY

LIME MODIFIED SOILS

LOCATION STATION TO STATION	PROCESSING MODIFIED SOILS 12"	LIME	FOR INFO. ONLY WATER
	SQ YD	TON	UNIT
IL 13 (EB)			
STA 1803+52 TO STA 1807+50	1292	38	19
STA 1818+00 TO STA 1822+50	1451	43	22
IL 13 (WB)			
STA 1802+97 TO STA 1807+50	1463	44	22
STA 1818+50 TO STA 1822+06.50	1151	34	17
TEMPORARY RAMP A			
STA 11+33.78 TO STA 12+86.21	739	22	11
TEMPORARY RAMP B			
STA 20+78.39 TO STA 21+80.91	605	18	9
TEMPORARY RAMP C			
STA 7+49.25 TO STA 8+82.20	593	18	9
PROJECT TOTAL	7294	217	109