

TEMPORARY PIPE CULVERTS

| LOCATION STATION TO STATION | TRENCH BACKFILL | PIPE CULVERTS, CLASS A, (TEMPORARY) | | | PRECAST REINFORCED CONCRETE FLARED END SECTIONS | | |
|----------------------------------|--------------------|---|-------------|-------------|--|-------------|-------------|
| | | TYPE 1 | | | 15" EACH | 18" EACH | 24" EACH |
| | | 15" FOOT | 18" FOOT | 24" FOOT | | | |
| | CU YD | | | | | | |
| IL 13 STA 1803+99.72 RT. | 11.2 | 59 | | | 1 | | |
| TEMPORARY RAMP A STA 12+41.36 | 92.0 | | | 95 | | | 2 |
| TEMPORARY RAMP B STA 21+00.00 | 13.7 | 45 | | | 2 | | |
| TEMPORARY RAMP C STA 8+32.97 | 17.8 | | 58 | | | 2 | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| PROJECT TOTAL | 135 | 104 | 58 | 95 | 3 | 2 | 2 |

DRAINAGE REMOVAL

| LOCATION STATION | CONCRETE HEADWALL REMOVAL EACH |
|-----------------------------|---|
| IL 13 RT. STA 1803+99.72 | 1 |
| | |
| PROJECT TOTAL | 1 |

SURFACE MOUNT LANE SEPARATOR (STATE OWNED)

| LOCATION STATION TO STATION | SURFACE MOUNT LANE SEPARATOR (STATE OWNED) FOOT |
|-------------------------------------|--|
| IL 13 STA 1804+42 TO STA 1805+42 | 100 |
| STA 1820+05 TO STA 1821+05 | 100 |
| | |
| PROJECT TOTAL | 200 |