

RESURFACING SCHEDULE FAP 869 (IL 14)

LOCATION - STATION TO STATION				LENGTH	PAVEMENT WIDTH	PAVEMENT AREA	SHOULDER WIDTH		MICRO-SURF., SINGLE PASS, TY. 2, MIX. D SHOULDER AREA		MICRO-SURF., SINGLE PASS, TY. 2, MIX. D PAVEMENT AREA	BIT. MATLS. (PR. CT.) (SEE NOTE 2)	FIBER-MOD. ASPHALT CR. SEAL (SEE NOTE 1)	
				FOR INFORMATIONAL PURPOSE ONLY				LEFT	RIGHT	LEFT				RIGHT
				(FT)	(FT)	(SQ YD)	(FT)	(FT)	(SQ YD)	(SQ YD)				(SQ YD)
FAP 869 (IL 14) Perry Co.														
	84+50	TO	179+32	9482	24.0	25285					25285	2275.7	18,964	
Lt.	84+50	TO	87+27	277			3.0		92			8.3	277	
Lt.	88+00			161		210				210		18.9	161	
Lt.	88+56	TO	116+40	2784			3.0		928			83.5	2,784	
Lt.	116+91			81		90				90		8.1	81	
Lt.	117+25	TO	168+78	5153			3.0		1718			154.6	5,153	
Lt.	169+50			163		191				191		17.2	163	
Lt.	170+06	TO	179+32	926			3.0		309			27.8	926	
Rt.	84+50	TO	116+57	3207				3.0		1069		96.2	3,207	
Rt.	116+91			77		94				94		8.4	77	
Rt.	117+19	TO	179+32	6213				3.0		2071		186.4	6,213	
SUB-TOTALS									3047	3140	25870			
TOTALS										32,057		2885.1	38,006	

Note 1: Fiber-Modified Asphalt Crack Seal is calculated using 1 lb. of material per 2.8 lineal foot. Use 1 strip each for each lane and shoulder on IL 14 through the length of the project, unless otherwise noted on plans.

Note 2: Bituminous Materials (Prime Coat) quantity includes shoulder and pavement areas.

PAVEMENT MARKING SCHEDULE

STATION TO STATION				THPL PAVEMENT MARKING		TEMPORARY		SHORT TERM PVT MARKING
				4 INCH WHITE (EDGELINE)	24 INCH WHITE (STOP BAR)	4 INCH (SKIP-DASH)	24 INCH (STOP BAR)	
				FOOT	FOOT	FOOT	FOOT	
FAP 869 (IL 14) PERRY COUNTY								
STA. 84+50 TO STA. 179+32								
	84+50.0	TO	179+32.0	2,371		2,371		1,896
LT	84+50.0	TO	87+27.0	277		277		
LT	88+00.0				12		12	
LT	88+56.0	TO	116+40.0	2,784		2,784		
LT	116+91.0				12		12	
RT	116+91.0				12		12	
LT	117+25.0	TO	168+78.0	5,153		5,153		
LT	169+50.0				12		12	
LT	170+06.0	TO	179+32.0	926		926		
RT	84+50.0	TO	116+57.0	3,207		3,207		
RT	117+19.0	TO	179+32.0	6,213		6,213		
TOTALS				20,931	48	20,931	48	1,896