STRUCTURE SCHEDULE

ID	LOCATION STATION	LT / RT	OFFSET	INLETS: TYPE A, TYPE 37 GRATE	INLETS: TYPE G-1	INLETS: TYPE G-1, DOUBLE (SPECIAL)	IN-MH: TYPE G-1, 5' DIA SPECIAL	IN-MH: TYPE G-1, 5' DIA, DOUBLE, SPECIAL	IN-MH: TYPE G-1, 6' DIA SPECIAL	IN-MH: TYPE A, 6' DIA TYPE 37 GRATE	MANHOLES: MANHOLES TO BE RECONSTRUCTED	MANHOLES: TYPE A, 6' DIA TIF, CI	PRECAST REINFORCED CONCRETE FLARED END SECTIONS: PRC 12"	PRC 15"	PRC 30"	ERS 36"	NOTE
					XX008440	X6020065	XX000321	X0325404	X0325442		60257900	60223800	54213657	54213660	54213675	54214521	
				EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	
EX-1	3353+60.00	RT	20.25								1						
1	3354+99.00	RT	63.72	1													
2	3355+26.00	RT	63.72	1													
3	3355+44.30	RT	13.00				1										
4	3355+44.30	LT	13.00		1												
5	3356+00.00	RT	13.00					1									
6	3357+00.00	RT	13.00				1										
6A	3357+00.00	LT	13.00		1												
7	3358+00.00	RT	13.00				1										
8	3359+50.00	RT	13.00				1										
9	3359+50.00	LT	13.00		1												
9A	3359+50.00	LT	24.00										1				
10	3360+10.00	RT	30.00	1													
11	3361+92.00	RT	47.00	1													
12	3362+27.00	RT	47.00	1													
13	3362+43.00	RT	13.00				1										
13A	3362+43.00	LT	13.00		1												
14	3364+00.00	LT	21.83										1				
15	3364+00.00	LT	13.00		1												
16	3364+00.00	RT	13.00				1										
17	3364+00.00	RT	26.11	1													
18A	3365+75.00	RT	13.00		1												
19A	3365+75.00	LT	13.00		1												
18	3367+50.00	RT	13.00		1												
19	3367+50.00	LT	13.00		1												
20	3369+50.00	RT	13.00		1												
20A	3369+50.00	LT	13.00		1												
21	3372+00.00	RT	13.00		1												
22	3372+00.00	LT	13.00		1												
21A	3374+00.00	RT	13.00		1												
22A	3374+00.00	LT	13.00		1												
23	3379+14.00	RT	31.34										1				
24	3379+06.00	RT	13.00			1											
25	3379+06.00	LT	13.00			1											
26	3379+25.55	RT	30.57													1	
27	3379+27.40	LT	26.00							1							
28	3380+00.00	LT	20.50									1					
29	3380+00.00	LT	26.46										1				
30	3380+37.01	LT	27.68						1								
31	3380+38.76	LT	57.18											1			
32	3380+89.56	LT	58.43											1			
33	3380+92.32	LT	27.66						1								
34	3381+10.00	LT	30.00									1					
35	3381+17.47	LT	27.52												1		
36	3379+39.66	RT	37.03										1				1
				6	15	2	6	1	2	1	1	2	5	2	1	1	

NOTES: 1. SALVAGE AND REUSE EXISTING PRECAST FLARED END SECTION 12"

PIPE SCHEDULE

ID	FROM STR.	TO STR.	PIPE CULVERTS, CLASS A, TYPE 1: ERS 36"	STORM SEWERS, CLASS A, TYPE 1: 12"	15"	21"	24"	30"	ERS 42"	TYPE 2: 12"	24"	TRENCH BACKFILL
			542A5491	550A0050	550A0070	550A0110	550A0120	550A0140	550A4700	550A0340	550A0410	20800150
			FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	CU YD
1	3	EX-1									179.6'	18.4
2	1	2		25.0'								1.7
3	2	3								47.4'		0.0
4	4	3								27.4'		3.7
5	5	3									47.2'	13.8
6	6	5									98.5'	19.2
6A	6A	6		27.4'								1.7
7	7	6					95.0'					10.1
8	8	7					145.0'					16.1
9	9	8		27.4'								1.9
9A	9A	9		7.6'								0.1
10	10	8		57.2'								0.3
11	13	8				288.0'						27.9
12	11	12		33.2'								2.5
13	12	13		31.4'								0.0
13A	13A	13		28.0'								1.8
14	16	13				152.0'						15.5
15	14	15		5.4'								0.0
16	15	16		27.4'								2.0
17	17	16		6.6'								0.0
18	18A	16			171.0'							13.0
18A	19A	18A		28.0'								1.8
18B	18	18A			172.0'							14.1
19	19	18		28.0'								2.0
20	20	18		197.0'								12.4
20A	20A	20		28.0'								1.4
21	21	20		247.0'								16.8
22	22	21		28.0'								1.8
22A	21A	21		197.0'								15.0
22B	22A	21A		28.0'								1.8
23	24	23		16.0'								0.4
24	25	24		28.0'								2.2
25	EX	26	2.4'									0.0
25A	27	EX	5.7'									0.0
26	28	27							68.7'			0.0
27	29	28		3.0'								0.0
28	30	28							31.1'			2.7
29	31	30			25.2'							0.0
30	33	30							54.5'			1.9
31	32	33			26.6'							0.0
32	34	33						11.0'				0.0
33	35	34						5.9'				0.0
34	EX	36		76.6'								0.0
			8'	1181'	395'	440'	240'	17'	154'	75'	325'	224

FILE NAME = s:\237\2010\23710006 (CentennialDriveSegmentIVPhII)\CADD\CADD Sheets\D489481-sht-sched.dgn	USER NAME = rmbradle	DESIGNED - BAB/RAW	REVISED -	MAURER & STUTZ, INC. ENGINEERS SURVEYORS	CENTENNIAL DRIVE PHASE IV DRAINAGE SCHEDULES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - BAB	REVISED -			6745	07-00130-03-PV	TAZEWELL	39	7
	PLOT SCALE = 39.9999 ' / IN.	CHECKED - RMB	REVISED -			CONTRACT NO. 89481				
	PLOT DATE = 3/15/2011	DATE - 03/02/2011	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT				