

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNITS	116
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNITS	156
20200100	EARTH EXCAVATION	CU YD	1,932
20800150	TRENCH BACKFILL	CU YD	165
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2,060
21101505	TOPSOIL EXCAVATION AND PLACEMENT,	CU YD	420
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	200
25000110	SEEDING, CLASS 1A	ACRE	0.80
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72
25000500	PHOSPOROUS FERTILIZER NUTRIENT	POUND	72
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72
25100115	MULCH, METHOD 2	ACRE	0.8
28000400	PERIMETER EROSION BARRIER	FOOT	275
28000500	INLET AND PIPE PROTECTION	EACH	43
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	1,400
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	490
35100100	AGGREGATE BASE COURSE, TYPE A,	TON	30
40300100	BITUMINOUS MATERIAL (PRIME COAT)	GAL	25
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COAT)	GAL	65
40300500	COVER COAT AGGREGATE	TON	2
40300600	SEAL COAT AGGREGATE	TON	1
42300200	PC CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	195
42300400	PC CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	230
42400100	PC CONCRETE SIDEWALK, 4 INCH	SQ FT	12,850
42400300	PC CONCRETE SIDEWALK, 6 INCH	SQ FT	590
42400410	PC CONCRETE SIDEWALK, 8 INCH	SQ FT	890
42400800	DETECTABLE WARNINGS	SQ FT	48
44000100	PAVEMENT REMOVAL	SQ YD	5
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	510
44000500	COMBINATION CONCRETE CURB & GUTTER REMOVAL	FOOT	305
44000600	SIDEWALK REMOVAL	SQ FT	5,670
44201765	CLASS D PATCHES, TYPE II, 10"	SQ YD	12
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	480
550A0360	STORM SEWERS, CLASS A, TYPE 2, 15"	FOOT	154
550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	136
550A0400	STORM SEWERS, CLASS A, TYPE 2, 21"	FOOT	156
55100500	STORM SEWER REMOVAL, 12"	FOOT	142
* 56106300	ADJUSTING WATER MAIN 6"	FOOT	250

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL
* 56400100	FIRE HYDRANTS TO BE MOVED	EACH	2
* 56500300	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	10
60218300	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME OPEN LID	EACH	5
60221000	MANHOLES, TYPE A, 5' DIAMETER, TYPE 1 FRAME OPEN LID	EACH	3
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2
60255500	MANHOLES TO BE ADJUSTED	EACH	10
60262900	INLETS TO BE RECONSTRUCTED W/ NEW TYPE 1 FRAME, OPEN LID	EACH	1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	2
60500040	REMOVING MANHOLES	EACH	4
60500060	REMOVING INLETS	EACH	5
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	2
60603400	CONCRETE CURB & GUTTER OUTLET (SPECIAL)	EACH	2
60604400	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18	FOOT	3,020
60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	FOOT	10
* 66900205	SPECIAL WASTE DISPOSAL	CU YD	10
* 66900500	BETX SOIL ANALYSIS	EACH	2
67100100	MOBILIZATION	L. SUM	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,350
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	280
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	270
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	55
LR420029	PC CONCRETE PAVEMENT 8" (SPECIAL)	SQ YD	5,125
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	3
X6020076	INLETS, TYPE SPECIAL, WITH SPECIAL FRAME & GRATE	EACH	29
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L. SUM	1
XX000061	STUMP REMOVAL	EACH	2
XX006239	STORM SEWER DUCTILE IRON 20"	FOOT	30
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1
Z0022800	FENCE REMOVAL	FOOT	25

* SPECIALTY ITEMS

EARTHWORK SCHEDULE SUMMARY - FOR INFORMATION ONLY							
EARTHWORK LOCATION	RAW EARTH EXCAVATION (CU YD)	TOPSOIL EXCAVATION & PLACEMENT (CU YD)		EARTH EXC. ADJUSTED (CU YD)	EARTH EXC. ADJUSTED FOR SHRINKAGE (25% S.F.) (CU YD)	EMBANKMENT INCLUDING TOPSOIL (CU YD)	EARTH EXCAVATION WASTE (+) OR SHORTAGE (-) (CU YD)
		CUT	FILL				
EAST MAIN STREET	1,888	44	376	1,932	1,449	857	+592
TOTAL	1,888	44	376	1,932	1,449	857	+592

DESIGNED - PJM/LAT	REVISED -
DRAWN - DRR	REVISED -
CHECKED - PJM	REVISED -
DATE - 12/01/10	REVISED -

CITY OF CLINTON

SUMMARY OF QUANTITIES

EAST MAIN STREET
SECTION 09-00047-00-RP
DeWITT, COUNTY

SCALE: SHEET NO. 3 OF 28 SHEETS STA. TO STA.

FIELD BOOK 2670				
F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7311	09-00047-00-RP	DeWITT	28	3
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 91432	