

SUMMARY OF QUANTITIES

F.A.U. RTE. 7982	SECTION *	COUNTY SANGAMON	TOTAL SHEETS 63	SHEET NO. 4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• 10-00447-04-PV		CITY OF SPRINGFIELD		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	
				CAPITOL AVENUE 10-00447-04-PV NON-ITEP ELIGIBLE ITEMS	CAPITOL AVENUE 10-00447-04-PV ITEP ELIGIBLE ITEMS
				0004	0031
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	10		10
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	369		369
Δ 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	7		7
Δ 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	8		8
20800150	TRENCH BACKFILL	CU YD	77		77
Δ 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	265		265
Δ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7		7
Δ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7		7
Δ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7		7
Δ 25200110	SODDING, SALT TOLERANT	SQ YD	265		265
Δ 25200200	SUPPLEMENTAL WATERING	UNIT	24		24
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	12		12
28000510	INLET FILTERS	EACH	15		15
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	2362		2362
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1016		1016
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	205	79	126
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1104	1086	18
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	182		182
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1237	1217	20
42000201	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SQ YD	1177		1177
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	1076		1076
42001300	PROTECTIVE COAT	SQ YD	5236	1317	3919
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	347	233	114
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	17884	7040	10845
* 42400800	DETECTABLE WARNINGS	SQ FT	446	446	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	10861	10861	

* PAY ITEM REQUIRES A SPECIAL PROVISION

Δ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAU RTE 7982 CAPITOL AVE
 SEC NO. 10-00447-04-PV
 SANGAMON COUNTY, ILLINOIS
 VERT. SCALE: DATE 11/19/10
 DRAWN BY: RSJ
 CHECKED BY: MH



© Copyright Hanson Professional Services Inc. 2011
 PLOT DATE = 01/09/2011
 FILE NAME = I:\02\jobs\0252041A\CADD\Road\MicroStation\Sheets\Section_3-11.dwg
 PLOT SCALE = 50.000 1 / in
 USER NAME = John@0944

LAYOUT	TCJ	03/27/07
DRAWN	TCJ	03/27/07
REVIEWED	MH	/ /