

**DECK SLAB RESTORATION-ROADWAY  
DECK SLAB REPAIR (PARTIAL)**

Spans	Area (SQ. YD.)
1 - 6	25.22
6 - 8	22.91
8 - 10	22.27
10 - 12	15.96
12 - 14	39.29
14 - 16	26.96
16 - 21	50.32
Total	202.93

**POLYMER OVERLAY PRETREATMENT**

SPANS	Area (SQ. YD.)
1-6	3.48
6-8	10.91
8-10	27.12
10-12	8.33
12-14	5.19
14-16	38.14
16-21	22.72
TOTAL	115.89

**SUMMARY -STRUCTURAL REPAIR OF CONCRETE**

SPANS	STRUCTURAL REPAIR OF CONCRETE (SQ FT)
2-4	130.25
5, 17	196.59
6	76.86
7	62.41
8	133.01
9	161.64
10	284.15
11	191.72
12	164.32
13	57.40
14	90.43
15	112.37
16	84.89
18-20	156.35
Vertical Repairs	899.63
Horizontal Repairs	1002.76
Subtotal	1902.39

**DECK SLAB RESTORATION-SIDEWALK  
DECK SLAB REPAIR (PARTIAL)**

Spans	Area (SQ. YD.)
1 - 6	18.51
6 - 8	9.52
8 - 10	32.28
10 - 12	48.53
12 - 14	20.19
14 - 16	2.75
16 - 21	2.16
Total	133.94

**BRIDGE DECK CONCRETE CRACK SEALER**

SPANS	FOOT
2-4	136
5	48
6	225
7	344
8	226
9	205
10	214
11	192
12	158
13	234
14	280
15	293
16	307
17	66
18-20	88
Subtotal	3016

**PAINT PAVEMENT MARKING - LINE 5"**

LOCATION	FOOT
DOUBLE YELLOW CENTERLINE	
STA 0+33 TO STA 14+27	2,788
TOTAL	2,788

**EXPANSION JOINT REPAIRS  
DECK SLAB REPAIR (PARTIAL)**

SPANS	EXPANSION JOINT REPAIRS (SQ. YD.)
1 - 6	22.36
6 - 8	12.16
8 - 10	12.16
10 - 12	12.16
12 - 14	12.16
14 - 16	12.16
16 - 21	22.36
TOTAL	105.52

(Includes area from face to face of railing curb)

**BRIDGE DECK THIN POLYMER OVERLAY, 3/8"  
(LIMITS: END-END BRIDGE, FACE-FACE  
RAILING INCLUDING SIDEWALKS)**

SPANS	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
1-5	177.00	35.92	706.43
6-16	1040.00	33.92	3919.64
17-21	177.00	35.92	706.43
TOTAL			5332.50