

EARTHWORK SCHEDULE						
STATION	EARTH EXCAVATION (CU.YD.)	CHANNEL EXCAVATION (CU.YD.)	ESTIMATED UNSUITABLE MATERIAL (CU.YD.)	SUITABLE MATERIAL ADJUSTED FOR SHRINKAGE (CU.YD.)	EMBANKMENT (CU.YD.)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU.YD.)
995+08.44 to 999+71.05	80	0	60	0	60	-80

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
GRCDT	10-00046-00-BT	MASSAC	36	5
FROM STA.	TO STA.			
FEDERAL PROJECT NO. TE-0009(121)			CONTRACT NO. 99429	

PAY ITEM RECAP										
PAY ITEM: SEEDING, CLASS 2										
ITEM CODE NO.: 25000200 0 NO. 3										
FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY					
995	+ 10	998	+ 70	360	100	ACRE				0.9
TOTAL										0.9

PAY ITEM RECAP										
PAY ITEM: NITROGEN FERTILIZER NUTRIENT										
ITEM CODE NO.: 25000400 0 NO. 4										
FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY					
995	+ 10	998	+ 70	360	61	POUND				81.0
TOTAL										81.0

PAY ITEM RECAP										
PAY ITEM: PHOSPHORUS FERTILIZER NUTRIENT										
ITEM CODE NO.: 25000500 0 NO. 5										
FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY					
995	+ 10	998	+ 70	360	61	POUND				81.0
TOTAL										81.0

PAY ITEM RECAP										
PAY ITEM: POTASSIUM FERTILIZER NUTRIENT										
ITEM CODE NO.: 25000600 0 NO. 6										
FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY					
995	+ 10	998	+ 70	360	61	POUND				81.0
TOTAL										81.0

PAY ITEM RECAP										
PAY ITEM: AGRICULTURAL GROUND LIMESTONE										
ITEM CODE NO.: 25000700 0 NO. 7										
FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY					
995	+ 10	998	+ 70	360	61	TON				1.8
TOTAL										1.8

PAY ITEM RECAP										
PAY ITEM: MULCH, METHOD 1										
ITEM CODE NO.: 25100105 0 NO. 8										
FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY					
995	+ 10	998	+ 70	360	5	ACRE				0.9
TOTAL										0.9

PAY ITEM RECAP										
PAY ITEM: PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH										
ITEM CODE NO.: 42400200 0 NO. 12										
FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY					
995	+ 08	999	+ 71	463	10	SQ FT				4787
TOTAL										4787

PAY ITEM RECAP										
PAY ITEM: DETECTABLE WARNINGS										
ITEM CODE NO.: 42400800 0 NO. 13										
FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY					
995	+ 10	995	+ 12	2	10	SQ FT				20
999	+ 66	999	+ 68	2	10	SQ FT				20
TOTAL										40

PAY ITEM RECAP										
PAY ITEM: SIDEWALK REMOVAL										
ITEM CODE NO.: 44000600 0 NO. 14										
FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY					
998	+ 70	998	+ 75	5	5	SQ FT				25
TOTAL										25

PAY ITEM RECAP										
PAY ITEM: PIPE CULVERT, CLASS C, TYPE I- 12"										
ITEM CODE NO.: 542C0217 0 NO. 15										
FROM STATION	TO STATION	LENGTH	WIDTH	UNIT	QUANTITY					
		995	+ 19			FOOT				20
TOTAL										20

PAY ITEM RECAP										
PAY ITEM: FRENCH DRAINS										
ITEM CODE NO.: 60100080 0 NO. 16										
FROM STATION	TO STATION	DEPTH	WIDTH	UNIT	QUANTITY					
995	+ 79 (L)	998	+ 63 (L)	2	2	CU YD				42.0
995	+ 79 (R)	998	+ 63 (R)	2	2	CU YD				42.0
TOTAL										84.0

PAY ITEM RECAP										
PAY ITEM: GEOTECHNICAL FABRIC FOR FRENCH DRAINS										
ITEM CODE NO.: 60100085 0 NO. 17										
FROM STATION	TO STATION	DEPTH	WIDTH	UNIT	QUANTITY					
995	+ 79 (L)	998	+ 63 (L)	2	10	SQ YD				316
995	+ 79 (R)	998	+ 63 (R)	2	10	SQ YD				316
TOTAL										632