

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	6,256	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L.S.	1	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	80	
AR125410	MITL - STAKE MOUNTED	EA.	23	
AR125415	MITL - BASE MOUNTED	EA.	4	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EA.	1	
AR125565	SPLICE CAN	EA.	1	
AR125961	RELOCATE STAKE MOUNTED LIGHT	EA.	4	
AR125962	RELOCATE BASE MOUNTED LIGHT	EA.	2	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	16,165	
AR155616	SOIL PROCESSING-16"	S.Y.	8,951	
AR155540	BY-PRODUCT LIME	TON	322	
AR156511	DITCH CHECK	EA.	5	
AR156521	HEADWALL PROTECTION	EA.	2	
AR156530	TEMPORARY SEEDING	ACRE	6.6	
AR156531	EROSION CONTROL BLANKET	S.Y.	1,825	
AR156544	RIPRAP-GRADATION NO. 4	S.Y.	373	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	5,065	
AR401613	BIT. SURF. CSE.-METHOD 1, SUPERPAVE	TON	1,020	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	93	
AR403613	BIT. BASE CSE.-METHOD 1, SUPERPAVE	TON	1,518	
AR602510	BITUMINOUS PRIME COAT	GAL.	3,015	
AR603510	BITUMINOUS TACK COAT	GAL.	1,320	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	2,789	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	350	
AR701006	6" PVC STORM SEWER	L.F.	100	
AR701008	8" PVC STORM SEWER	L.F.	100	
AR701010	10" PVC STORM SEWER	L.F.	100	
AR701560	60" RCP, CLASS IV	L.F.	160	
AR701566	66" RCP, CLASS IV	L.F.	238	
AR705410	POROUS BACKFILL	C.Y.	96	
AR705524	4" PERFORATED UNDERDRAIN W/SOCK	L.F.	3,930	
AR705620	UNDERDRAIN END SECTION	EA.	1	
AR705630	UNDERDRAIN INSPECTION HOLE	EA.	11	
AR705900	REMOVE UNDERDRAIN	L.F.	140	
AR705903	REMOVE UNDERDRAIN INSP. HOLE	EA.	1	
AR752460	PRECAST REINFORCED CONC. FES 60"	EA.	1	
AR752466	PRECAST REINFORCED CONC. FES 66"	EA.	1	
AR752660	CONCRETE HEADWALL 60"	EA.	1	
AR752666	CONCRETE HEADWALL 66"	EA.	1	
AR754910	REMOVE PAVED DITCH	L.F.	241	
AR800463	FIELD TILE REPAIR	EA.	5	
AR800531	CLEAN & RESHAPE PAVED DITCH	L.F.	1,243	
AR901510	SEEDING	AC.	6.6	
AR908510	MULCHING	AC.	6.2	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED STORMWATER POLLUTION PREVENTION PLAN
5	PROPOSED CONSTRUCTION PLAN STA. 65+76 TO STA. 72+00
6	PROPOSED CONSTRUCTION PLAN STA. 72+00 TO STA. 80+00
7	PROPOSED CONSTRUCTION PLAN STA. 80+00 TO STA. 85+76
8	PROPOSED PLAN AND PROFILE STA. 65+00 TO STA. 73+00
9	PROPOSED PLAN AND PROFILE STA. 73+00 TO STA. 81+00
10	PROPOSED PLAN AND PROFILE STA. 81+00 TO STA. 88+00
11	PROPOSED STAKING PLAN STA. 65+76 TO STA. 72+00
12	PROPOSED STAKING PLAN STA. 72+00 TO STA. 80+00
13	PROPOSED STAKING PLAN STA. 80+00 TO STA. 85+76
14	EXISTING DRAINAGE PLAN STA. 65+75.24 TO STA. 74+00
15	EXISTING DRAINAGE PLAN STA. 74+00 TO STA. 82+00
16	EXISTING DRAINAGE PLAN STA. 82+00 TO STA. 87+00
17	PROPOSED DRAINAGE PLAN STA. 65+00 TO STA. 72+00
18	PROPOSED DRAINAGE PLAN STA. 72+00 TO STA. 80+00
19	PROPOSED DRAINAGE PLAN STA. 80+00 TO STA. 86+00
20	EXISTING ELECTRICAL RELOCATION PLAN
21	PROPOSED ELECTRICAL PLAN STA. 65+75.24 TO STA. 74+00
22	PROPOSED ELECTRICAL PLAN STA. 74+00 TO STA. 82+00
23	PROPOSED ELECTRICAL PLAN STA. 82+00 TO STA. 87+00
24	ELECTRICAL DETAILS SHEET 1
25	ELECTRICAL DETAILS SHEET 2
26	ELECTRICAL DETAILS SHEET 3
27	ELECTRICAL NOTES SHEET 1
28	ELECTRICAL NOTES SHEET 2
29	ELECTRICAL LEGEND AND ABBREVIATIONS
30	EXISTING FLOOR PLAN FOR VAULT
31	EXISTING ELECTRICAL ONE LINE DIAGRAM FOR VAULT
32	PROPOSED FLOOR PLAN FOR VAULT
33	PROPOSED ELECTRICAL ONE LINE DIAGRAM FOR VAULT
34	RUNWAY 18-36 LIGHTING CONTROL SCHEMATIC
35	HIGH VOLTAGE WIRING SCHEMATIC
36	CCR GROUND BUS RISER
37	GROUNDING DETAILS
38	GROUNDING NOTES
39	LEGEND PLATE SCHEDULE
40	PROPOSED MARKING PLAN STA. 65+75 TO STA. 74+00
41	PROPOSED MARKING PLAN STA. 74+00 TO STA. 85+58
42	CROSS-SECTIONS FOR TAXIWAY C STA. 65+00 TO STA. 65+75.97
43	CROSS-SECTIONS FOR TAXIWAY C STA. 66+00 TO STA. 66+10.97
44	CROSS-SECTIONS FOR TAXIWAY C STA. 66+45.97 TO STA. 67+00
45	CROSS-SECTIONS FOR TAXIWAY C STA. 67+50 TO STA. 68+00
46	CROSS-SECTIONS FOR TAXIWAY C STA. 68+50 TO STA. 69+00
47	CROSS-SECTIONS FOR TAXIWAY C STA. 69+25.18 TO STA. 69+50
48	CROSS-SECTIONS FOR TAXIWAY C STA. 69+80.28 TO STA. 70+00
49	CROSS-SECTIONS FOR TAXIWAY C STA. 70+50 TO STA. 71+00
50	CROSS-SECTIONS FOR TAXIWAY C STA. 71+50 TO STA. 72+00
51	CROSS-SECTIONS FOR TAXIWAY C STA. 72+50 TO STA. 73+00
52	CROSS-SECTIONS FOR TAXIWAY C STA. 73+50 TO STA. 73+63.86
53	CROSS-SECTIONS FOR TAXIWAY C STA. 74+00 TO STA. 74+50
54	CROSS-SECTIONS FOR TAXIWAY C STA. 75+00 TO STA. 75+50
55	CROSS-SECTIONS FOR TAXIWAY C STA. 76+00 TO STA. 76+50
56	CROSS-SECTIONS FOR TAXIWAY C STA. 77+00 TO STA. 77+50
57	CROSS-SECTIONS FOR TAXIWAY C STA. 78+00 TO STA. 78+50
58	CROSS-SECTIONS FOR TAXIWAY C STA. 79+00 TO STA. 79+50
59	CROSS-SECTIONS FOR TAXIWAY C STA. 80+00 TO STA. 80+50
60	CROSS-SECTIONS FOR TAXIWAY C STA. 81+00 TO STA. 81+50
61	CROSS-SECTIONS FOR TAXIWAY C STA. 82+00 TO STA. 82+50
62	CROSS-SECTIONS FOR TAXIWAY C STA. 83+00 TO STA. 83+50
63	CROSS-SECTIONS FOR TAXIWAY C STA. 84+00 TO STA. 84+50
64	CROSS-SECTIONS FOR TAXIWAY C STA. 85+00 TO STA. 85+12
65	CROSS-SECTIONS FOR TAXIWAY C STA. 85+50 TO STA. 85+58.50
66	CROSS-SECTIONS FOR TAXIWAY C STA. 86+00
67	CROSS-SECTIONS FOR TAXIWAY C3 STA. 302+00 TO STA. 302+50
68	CROSS-SECTIONS FOR TAXIWAY C3 STA. 303+00 TO STA. 303+27.50
69	CROSS-SECTIONS FOR TAXIWAY C3 STA. 303+82.50 TO STA. 304+00
70	CROSS-SECTIONS FOR TAXIWAY C3 STA. 304+17.50 TO STA. 304+50

BY	
REVISION	
DATE	

LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS

IL PROJ.: 31F-4046 A.I.P. PROJ.: 3-17-0063-B17

Hanson Project No. 10A0094D_0800	BAK	06/28/10
Filename R-002FLP.DWG	BAK	06/28/10
Scale NOT TO SCALE	CAH	02/17/11
Date 02/04/11		
LAYOUT		
DRAWN		
REVIEWED		



Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2886  
Offices Nationwide

TAXIWAY "C"  
EXTENSION

SUMMARY OF QUANTITIES  
AND INDEX TO SHEETS

MAR 18, 2011 2:38 PM HAGL000382 I:\AIRPORTS\LITCHFIELD\10A0094\CADD\AIRPORT\SHEET\R-002FLP.DWG - SUMMARY OF QUANTITIES AND INDEX TO SHEETS