



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 13, 2022

SUBJECT FAP Route 327 (US 50/ US 45)
Project NHPP-KM91(374)
Section (8-2)RS-1
Clay County
Contract No. 74A07
Item No. 61, April 29, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised Table of Contents of the Special Provisions.
3. Revised Page 8 of the Special Provisions.
4. Revised Sheets 7 and 39 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
TRAFFIC CONTROL PLAN	2
ADA CURB RAMPS	3
BORROW AREAS, USE AREAS, AND/OR WASTE AREAS	5
CHANGEABLE MESSAGE SIGNS	5
CONCRETE MEDIAN, TYPE SB-6.06 (DOWELLED)	5
ELECTRIC CABLE IN CONDUIT	5
ISLAND REMOVAL	6
PARTIAL DEPTH PAVEMENT PATCHING	6
ACCESSIBLE PEDESTRIAN SIGNALS	8
PEDESTRIAN PUSH-BUTTON POST	8
PROTECTING OR RESETTING SURVEY MARKERS	9
RUMBLE STRIPS	10
SURFACE REMOVAL, VARIABLE DEPTH (SPECIAL)	10
TEMPORARY RAMP, SPECIAL	10
UNDERGROUND CONDUIT	11
ACCESSIBLE PEDESTRIAN SIGNALS (APS) (BDE)	12
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	13
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	14
BLENDED FINELY DIVIDED MINERALS (BDE)	16
COMPENSABLE DELAY COSTS (BDE)	16
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	20
FUEL COST ADJUSTMENT (BDE)	28
HOT-MIX ASPHALT – START OF PRODUCTION (BDE)	30
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE)	31
STEEL COST ADJUSTMENT (BDE)	32
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	34
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	35
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	35
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	41
WEEKLY DBE TRUCKING REPORTS (BDE)	41
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	41
WORKING DAYS (BDE)	43





ACCESSIBLE PEDESTRIAN SIGNALS

This work shall consist of furnishing and installing pedestrian pushbuttons of the type specified in accordance with Section 888 and Article 1074.02 of the Standard Specifications and Accessible Pedestrian Signals (APS) (BDE), except as modified herein.

The pushbuttons shall meet ADA requirements. All pedestrian pushbuttons shall have a case and be equipped with a 2" diameter button for easy access. The push buttons shall have a yellow housing and utilize a solid-state switch or reed relay. The following model is approved within the district: Polara iN2 Navigator 2-wire Push Button Station (iN2PBS) or an approved equal.

The pedestrian pushbutton shall be in a modular station assembly accommodating the size of sign listed below (9x15). The pushbutton will be part of the modular station with a four-hole mount round cover assembly.

The pedestrian pushbutton installation shall include all crossing signs and hardware required to mount the pedestrian pushbutton. All hardware shall be of stainless-steel construction. All bolts shall be Hex Head and no self tapping/drilling screws will be allowed. Anti-seize paste shall be installed on all fasteners.

All signs for pedestrian pushbutton shall be MUTCD sign R10-3e. All signs **shall not** be digitally printed.

This work will be paid for at the contract unit price per EACH for ACCESSIBLE PEDESTRIAN SIGNALS.

PEDESTRIAN PUSH-BUTTON POST

This work shall consist of furnishing and installing pedestrian push-button posts of the type and material specified in accordance with Section 876 of the Standard Specifications, except as described herein.

The pedestrian push-button post shall be GALVANIZED STEEL unless otherwise specified in the plans.

This work will be paid for at the contract unit price per EACH for PEDESTRIAN PUSH-BUTTON POST of the type and material specified.

Revised 4-13-2022