

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE 75% FEDERAL 25% LOCAL 0005
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	245	245
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	500	500
20400800	FURNISHED EXCAVATION	CU YD	10	10
20800150	TRENCH BACKFILL	CU YD	7	7
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	121	121
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	20	20
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	20	20
25100630	EROSION CONTROL BLANKET	SQ YD	121	121
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20	20
28000305	TEMPORARY DITCH CHECKS	FOOT	400	400
28000400	PERIMETER EROSION BARRIER	FOOT	62	62
35101400	AGGREGATE BASE COURSE, TYPE B	TON	830	830
LR400899	FULL-DEPTH RECLAMATION, 10"	SQ YD	14,555	14,555
35200500	CEMENT	100 WT	9,750	9,750
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	13,775	13,775
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	6,806	6,806

- SPECIAL PROVISION
- + SPECIALTY ITEM
- X CONSTRUCTION TYPE CODE 0042

△ REVISED 4/21/2022

HRG PROJECT NO. 200761
 HRG PROJ. CONTACT
 FILE NAME: 200761-02-Anderson
 PEN: TABLE: 200761-02-Anderson



USER NAME = jhrwtk	DESIGNED - JCH	REVISED * - XX/XX/XXXX
PLOT SCALE = 2,000' / in.	DRAWN - DMS	REVISED - XX/XX/XXXX
PLOT DATE = 2/17/2022	CHECKED -	REVISED - XX/XX/XXXX
	DATE -	REVISED - XX/XX/XXXX

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ANDERSON ROAD

SCALE: N.T.S. SHEET 1 OF 3 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2330	20-06000-02-FP	KANE	46	3
			CONTRACT NO. 61H60	
ILLINOIS FED. AID PROJECT				