

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FED 20% ST	
				ROADWAY	RURAL
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	87998	87998	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	145	145	1
* 66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	20	20	1
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
* 66901006	REGULATED SUBSTANCES MONITORING	CA DAY	2	2	1
67100100	MOBILIZATION	L SUM	1	1	
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	14323	14323	
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	1592	1592	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	169.4	169.4	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7208	7208	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	770	770	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1115	1115	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	298	298	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	191590	191590	

*= SPECIALTY ITEM

MODEL: Default
FILE: \\nas01c-pw-bentley.com\FWIDOT\Documents\DOT_Offices\DrHdt: 3\Projects\366690\CaddData\CaddSheets\366690-rt-S00.dgn

USER NAME = longneckerjh	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 2/21/2022	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(24,25)R5-3	LIVINGSTON	21	5
CONTRACT NO. 66L90			ILLINOIS FED. AID PROJECT	