

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80%FED/20%STATE NHPP FAP 330	80%FED/20%STATE NHPP FAP 332
				ROADWAY	ROADWAY
				0005 RURAL	0005 RURAL
40604162	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	11077	10129	948
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	603	575	29
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	224627	209169	15458
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	575	479	96
44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	36	36	
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	27	27	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	6871	6549	322
60920024	PIPE CULVERTS TO BE CLEANED 24"	FOOT	304	304	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1600	1600	
* 63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	7	7	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	7	7	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7	7	
63200310	GUARDRAIL REMOVAL	FOOT	1712.5	1712.5	
63500105	DELINEATORS	EACH	42	38	4
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	99089	89843	9246

\*= SPECIALTY ITEM



MODEL: Default  
FILE: \\nas01c-paw.bentley.com\PIV\DOT\Documents\DOT\_Offices\DH\dtdt\_3\Projects\0366673\0366673-shc-cover.dgn

USER NAME = pletschtr	DESIGNED - AC	REVISED - _____
DRAWN - AC	REVISIONS - _____	
PLOT SCALE = 100.0000' / in.	CHECKED - DC	REVISED - _____
PLOT DATE = 2/4/2022	DATE - 1/19/2022	REVISED - _____

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>			
SCALE: _____	SHEET 2 OF 4 SHEETS	STA. _____	TO STA. _____

F.A.P. RTE. 330/332	SECTION (1R,1R-1)RS-3	COUNTY KANKAKEE	TOTAL SHEETS 26	SHEET NO. 4
			CONTRACT NO. 66L73	
ILLINOIS FED. AID PROJECT				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80%FED / 20%STATE NHPP FAP 330	80%FED / 20%STATE NHPP FAP 332
				ROADWAY 0005 RURAL	ROADWAY 0005 RURAL
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	0.5	0.5
X0326341	REATTACH END SECTION	EACH	5	5	
X0327809	LINEAR DELINEATOR PANELS, 4 INCH	EACH	21	21	
X1400439	REMOTE CONTROLLED VIDEO SYSTEM	EACH	1	0.5	0.5
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	5422	5083	339
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	148	148	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	63	21	42
* Z0033072	VIDEO VEHICLE DETECTION SYSTEM	EACH	1	0.5	0.5
Z0034105	MATERIAL TRANSFER DEVICE	TON	11077	10129	948



\*= SPECIALTY ITEM

MODEL: Default  
FILE: \\nas01c-pw-bentley.com\PW\DOT\Documents\DOT\_Offices\DH\dtr\_3\Projects\0366L73\CADD\Drawn\0366L73-shc-cover.dgn

USER NAME = pletschtr	DESIGNED - AC	REVISED - _____
DRAWN - AC	CHECKED - DC	REVISED - _____
PLOT SCALE = 100.0000' / in.	DATE - 1/19/2022	REVISED - _____
PLOT DATE = 2/8/2022		

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>	
SCALE: _____	SHEET 4 OF 4 SHEETS STA. _____ TO STA. _____

F.A.P. RTE. 330/332	SECTION (1R,1R-1)RS-3	COUNTY KANKAKEE	TOTAL SHEETS 26	SHEET NO. 7
CONTRACT NO. 66L73			ILLINOIS FED. AID PROJECT	

GUARDRAIL SCHEDULE										
STRUCTURE	QUAD	EXISTING	LENGTH	SPBGR	TRAF BAR	TRAF BAR	GUARDRAIL	TERM	GUARDRAIL	LINEAR
		LENGTH	OF	TYP A	TERM TYP 1	TERM TYP 5A	REFLECTORS	MARK	REMOVAL	DELINEATOR
		GR	NEED	6' POST	(SPL) TANGENT		TYPE A	DA	FOOT	PANELS 4"
		FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	FOOT	EACH
SN 046-0037	NW	187.5	NO WORK				3	1	NONE	2
	SW	200'	212.5	162.5	1	1	3	1	200'	2
SN 046-0038	SE	212.5	187.5	137.5	1	1	3	1	212.5	2
	NE	200	212.5	162.5	1	1	3	1	200	
SN 046-0039	NW	312.5	262.5	212.5	1	1	4	1	312.5	3
	SW	150	262.5	212.5	1	1	4	1	150	3
SN 046-0040	NE	550	550	500	1	1	7	1	550	6
	SE	287.5	262.5	212.5	1	1	4	1	287.5	3
TOTALS				1600.0	7	7	31	8	1712.5	21

ILL. RTE. 17 LOCATION: 0.1 MI E OF LOWE RD E OF KANKAKEE TO 0.5 MI E OF IL 1 IN SUN RIVER TERRACE KANKAKEE COUNTY COUNTY

GPS NUMBER	DESCRIPTION	APPROXIMATE LOCATION	EXISTING MONUMENT TYPE	PROPOSED MONUMENT TYPE	MONUMENT RECORD TO BE RECORDED	RESPONSIBILITY
A017081	NW CORNER SECTION 1, T30N, R13W, 2ND PM	STA 112+40 WEST BOUND LANE	BRASS DISK	TYPE 1	NO	1
017083	SE CORNER SECTION 36, T31N, R12E, 3RD PM	STA 153+03 WEST BOUND LANE	BURIED DISK	TYPE 1	YES	1
017084	NE CORNER SECTION 1, T30N, R13W, 2ND PM	STA 164+66 WEST BOUND LANE	BURIED DISK	TYPE 1	YES	1
017088	SE CORNER SECTION 32, T31N, R13E, 3RD PM	STA 260+00 EAST BOUND LAND	BURIED DISK	TYPE 1	YES	1
PI3034500	PI STA 303+45.00 SBI RTE 17 = STA 400+00.00 SBI RTE 1	STA 303+45.00	BURIED DISK	TYPE 1	NO	1
PT314660	PT STA 31+46.60 BACK = STA 30+96.15 AHEAD SBI 1 SECTION (6.7,K,D)W-RS)	STA 311+00 +/-	POSSIBLE BURIED DISK	MAG SPIKE	NO	2
017090	E QTR CORNER SECTION 33, T31N, R13E, 3RD PM	STA 325+00 +/-	MAG NAIL	TYPE 1	YES	1
PC229740	PC STA 22+97.40 SBI 1 SECTION (6.7,K,D)W-RS)	STA 326+25 +/-	POSSIBLE BURIED DISK	MAG SPIKE	NO	2

ONLY THE ORIGINAL SCOPE OF THIS JOB HAS BEEN SEARCHED FOR MONUMENTS. R.E. MUST INFORM PLATS AND PLANS TO SEARCH FOR ADDITIONAL MONUMENTS PRIOR TO MILLING IF ADDENDUMS HAVE BEEN ADDED TO THIS JOB.

R.E. WILL INFORM PLATS AND PLANS WHEN CONSTRUCTION STARTS, FOR THE PURPOSE OF RECOVERING MONUMENTS LABELED "BURIED".

UNKNOWN MONUMENTS MAY EXIST. IF AN UNLISTED MONUMENT IS FOUND, R.E. IS REQUIRED TO PROTECT THE MONUMENT FROM DAMAGE UNTIL A PLATS AND PLANS LAND SURVEYOR CAN DOCUMENT THE MONUMENT. PLATS AND PLANS WILL RESET SUCH MONUMENTS IN KIND FOLLOWING CONSTRUCTION.

UPON PAVING COMPLETION, R.E. WILL DIRECT PLATS AND PLANS TO STAKE THE TYPE 1 PSM CORING LOCATION(S).

NOTE: FOR BIDDING PURPOSES NO CONTRACTED LAND SURVEYING SERVICES WILL BE REQUIRED.

PLATS AND PLANS WILL PREPARE THE REQUIRED MONUMENT RECORDS.

**RESPONSIBILITY:**

- 1) RESIDENT TO RE-ESTABLISH MONUMENT (PAY ITEM REQUIRED. PERMANENT SURVEY MARKER, TYPE 1)
- 2) PLATS AND PLANS TO RE-ESTABLISH MONUMENT

MODEL: Default  
 FILE: \\s:\11\it-ew-bentley.com\PIV\DOT1\Documents\DOT1\Office\81661\731\CAD\81661-731-eh-schedule.dgn

USER NAME = pletschtr	DESIGNED - _____	REVISED - _____
DRAWN - _____	REVISIONS - _____	
PLOT SCALE = 100.0000 ' / in.	CHECKED - _____	REVISIONS - _____
PLOT DATE = 2/4/2022	DATE - _____	REVISED - _____

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULES			
SCALE:	SHEET	OF	SHEETS
STA. _____	TO STA. _____		

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330/334	(1R,1R-1)RS-3	KANKAKEE	26	14
CONTRACT NO. 66L73				ILLINOIS FED. AID PROJECT