



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 13, 2022

SUBJECT: FAP Route 567 (IL 38)  
Project NHPP-STP-COVD-U1CQ(417)  
Section (7,6)RS-3  
DeKalb County  
Contract No. 66J64  
Item No. 172, April 29, 2022 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page 6 of the Special Provisions.
3. Revised sheets 4 and 31-32 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

### **SPECIAL GRATE NO. 1**

This work consists of providing a custom frame and grate that is ADA compliant for areas as shown in the plans.

The contractor shall supply an ADA compliant frame and grate with half-inch (1/2") openings that are perpendicular to the dominant pedestrian path. The supplied frame and grate shall be installed on the proposed depressed curb gutter and be compatible with the existing inlet system. Installation methods shall be discussed with the Engineer.

The cost of adjusting the frame and grate to the proposed grades shall be included in the cost of this pay item.

The contractor shall verify existing field dimensions before ordering the new material and shall provide shop drawings for approval by the Engineer. The proposed fabricated material shall be compliant to the requirements of Article 604.03 for frame and grates.

Basis of Payment. The work described herein shall be paid for at the contract unit price per Each for SPECIAL GRATE NO. 1.

### **RESET GRATE**

This item shall consist of resetting and mounting the grate to the existing end section at the locations shown in the plans. The contractor shall provide a suitable plan for reattaching the grate before beginning the work.

The payment for RESET GRATE shall include all hardware and labor for resetting and mounting the existing grate to the existing end section.

This work shall be measured and paid for at the contract unit price of Each for RESET GRATE.

### **PREPARATION OF SIDEWALK WORK AREAS**

(Revised April 4, 2022)

At any location where the existing sidewalk elevations require modification to meet ADA compliance, the work shall include leveling and shaping of the existing ground/subbase to provide the required ADA compliant slopes as shown in the plan details, including any required furnished excavation, earth excavation under the proposed sidewalk necessary to complete the work and restore any disturbed areas.

This work will not be paid for separately, but shall be included in the cost of the applicable sidewalk pay items:

- PORTLAND CEMENT CONCRETE SIDEWALK, 5"
- CONCRETE ISLAND, SPECIAL

Earth Excavation required for the removal of non-special waste disposal will be measured and paid separately.

The 4-Inch Aggregate Base Course, Type B (CA 6 material) required for the sidewalks will be measured and paid separately.

Revised April 13, 2022