

ADA SIDEWALK SCHEDULE

LOCATION	QUADRANT	RESP (2)	SW REM	CC&G REM	ISLAND REM	PAVT REM	PCC SW 5"	PCC ISLAND (SPL)	AGG BSE CSE TB 4"	PROTEC. COAT	DETECT WARNING	COMB CONC CC&G		HAND-HOLE TO BE ADJ	FRAME & LIDS TO BE AJD	WATER VALVE TO BE ADJ	GAS VALVE TO BE ADJ	INLETS TO BE ADJ	SPL GRATE NO. 1	SOD	SUPPL WATER	
			SQ FT	FOOT	SQ FT	SQ YD	SQ FT	SQ FT	SQ YD	SQ YD	SQ FT	TY B 6.12	TY B 6.24	EACH	EACH	EACH	EACH	EACH	EACH	SQ YD	UNIT	
			NHPP URBAN																			
(1)	5TH ST	SW	DEKALB	35.9	13			35.9		4.0		8.8	13								0.0	0.000
(1)	5TH ST	SE	DEKALB	305.4	23			305.4		33.9		8.0	12	1							0.0	0.000
	6TH ST	NW	DEKALB	NO WORK						0.0												
(1)	6TH ST	NE	DEKALB	285.4	30			285.4		31.7		24.4	30	1				1			0.0	0.000
(1)	6TH ST	SE	DEKALB	196.2	19			196.2		21.8		13.8	19					1			0.0	0.000
	7TH ST	NW	STATE	181.4	20			181.4		20.2		20.2	20			1					0.0	0.000
(1)	7TH ST	NE	STATE	249.7	30			249.7		27.7		27.3	30	2							0.0	0.000
(1)	7TH ST	SW	STATE	146.6	21			146.6		16.3		17.5	21					1			3.4	0.041
(1)	7TH ST	SE	STATE	189.3	35			189.3		21.0		24.1	35	2		1					0.0	0.000
	8TH ST	NW	DEKALB	78.0	24			78.0		8.7		22.2	24								3.8	0.046
(1)	8TH ST	NE	DEKALB	144.4	15			144.4		16.0		17.3	15								5.9	0.071
(1)	8TH ST	SW	DEKALB	131.0	14			131.0		14.6		18.7	14	1							0.0	0.000
	8TH ST	SE	DEKALB	119.6	14			119.6		13.3		8.2	14	1							8.0	0.096
	9TH ST	NW	DEKALB	185.0	15			169.1		18.8		8.5	15								14.9	0.179
(1)	9TH ST	NE	DEKALB	136.3	11			136.4		15.2		8.7	11								7.1	0.085
(1)	9TH ST	SW	DEKALB	151.0	17			151.0		16.8		16.9	17								4.1	0.049
	9TH ST	SE	DEKALB	168.3	19			168.3		18.7		14.8	19								11.4	0.137
	10TH ST	NW	STATE	282.3	42			288.7		32.1		43.4	42	1							11.3	0.136
(1)	10TH ST	NE	STATE	303.0	45			315.1		35.0		39.6	45								7.7	0.092
	10TH ST	SW	STATE	251.8	34			251.8		28.0		50.7	34								10.7	0.128
	10TH ST	SE	STATE	204.2	32			204.2		22.7		45.8	32								8.9	0.107
	11TH ST	NW	STATE	235.3	20			235.3		26.1		31.9	20			1				1	13.7	0.164
	11TH ST	NE	STATE	152.6	16			152.6		17.0		16.2	16							1	12.1	0.145
	11TH ST	SW	STATE	131.6	13			131.6		14.6		14.7	13			1	1				9.2	0.110
	11TH ST	SE	STATE	148.4	15			148.4		16.5		14.9	15		1						10.6	0.127
	EVANS AVE	SW	DEKALB	113.8	12			113.8		12.6		16.2	12								8.6	0.103
(1)	EVANS AVE	SE	DEKALB	125.9	15			125.9		14.0		21.9	15				1				8.5	0.102
	STA 75+15 (RXR)	NW	STATE	23.8	0			23.8		2.6		9.5									0.0	0.000
(1)	STA 75+15 (RXR)	NE	STATE	21.6	0			21.6		2.4		9.8									0.0	0.000
(1)	STA 75+15 (RXR)	SW	STATE	23.6	0			23.6		2.6		9.0									0.0	0.000
(1)	STA 75+15 (RXR)	SE	STATE	24.8	0			24.8		2.8		9.0									0.0	0.000
	DODGE AVE	NW	DEKALB	149.4	23			149.4		16.6		16.6	23								7.8	0.094
(1)	DODGE AVE	NE	DEKALB	138.7	23			138.7		15.4		20.6	23								3.0	0.036
(1)	SIMONDS AVE	SW	DEKALB	99.6	15			99.6		11.1		10.8	15								7.3	0.088
(1)	SIMONDS AVE	SE	DEKALB	117.1	10			117.1		13.0		11.8	10								3.5	0.042
	ELM ST	NW	DEKALB	158.3	25			158.3		17.6		19.2	25								8.9	0.107
	ELM ST	NE	DEKALB	176.8	29			176.8		19.6		21.8	29								9.1	0.109
	HOLLY ST	NW	DEKALB	180.1	33			180.1		20.0		12.0	33		1			1			9.9	0.119
	HOLLY ST	NE	DEKALB	195.7	15			195.7		21.7		26.3	15				1		1		0.0	0.000

NOTES:
 CURB AND GUTTER JOINTS & REINFORCEMENT SHALL FOLLOW HWY STNDS 606001 & 420001
 FERTILIZER - NITROGEN, POTASSIUM AND PHOSPHOROUS APPLICATION SHALL BE INCLUDED IN THE COST OF THE SODDING PAY ITEM AT A RATE OF 60 LBS/ACRE
 SUPPLEMENTAL WATERING - **4 ADDITIONAL WATERINGS** (3 GAL / SQ YD) WERE USED TO ESTIMATE QUANTITIES. INCREASE WATERING & ADJUST APPLICATION RATE IF JUSTIFIED AS PER ART 252.09 OF THE STANDARD SPECIFICATIONS.
 (1) - ENVIRONMENTAL CONDITIONS EXIST - PLEASE SEE SPECIAL PROVISIONS
 (2) - LOCAL AGENCY ONLY RESPONSIBLE FOR SIDEWALK REMOVAL

MODEL: \\MODELM\MAHFS
 FILE: MAHFS - 606001 - 420001 - ADA SIDEWALK SCHEDULE.dgn

USER NAME = calderoni	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 4/4/2022	DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES			
SCALE:	SHEET 12	OF 16 SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	(7,6)RS-3	DEKALB	101	31
			CONTRACT NO. 66J64	
ILLINOIS FED. AID PROJECT				

