

ITEM NO.	ITEMS	UNIT	URBAN QUANTITY	TRAFFIC SIGNALS												SIDEWALK		WATER MAIN	COSTCO	
				ROADWAY	LIGHTING	LANDSCAPING	IL RTE 56 & TRANS AM	22nd ST & IL ROUTE 56	22nd ST & MIDWEST RD	22nd ST & OAKBROOK PLAZA	22nd ST & MACARTHUR DRIVE	22nd ST & PARKVIEW DR	22nd ST & IL RTE 83	INTER-CONNECT	EMERGENCY VEHICLE PREEMPTION	80% FED 10% STATE 10% OAK BROOK	80% FED 10% STATE 10% OAKBROOK TERR	100% OAK BROOK	100% OAK BROOK	
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	SFTY-1B	SFTY-1B	Y060	J000-2A
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	11,128	J000-2A	Y030-1E	Y003	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	SFTY-1B	SFTY-1B	Y060	J000-2A
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	22,016				850	5,200	4,299	3,523	4,060	4,060	3,371	3,282	3,371					
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	7,782				600	1,630	1,865	1,025	941	941		780						
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	49,184					7,929	9,940	6,474	6,584	6,584	3,440	4,790	3,440					
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	833					246	48	188	160	160		31						
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1					1												
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	7					2		1	1	1	1		1					
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	8					1	2	1	1	1		2						
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1					1												
* 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1												1					
* 87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1							1										
* 87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	2								1				1					
* 87700320	STEEL MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1							1										
* 87700340	STEEL MAST ARM ASSEMBLY AND POLE, 58 FT.	EACH	1								1									
* 87700414	STEEL MAST ARM ASSEMBLY AND POLE, 66 FT.	EACH	1												1					
* 87700418	STEEL MAST ARM ASSEMBLY AND POLE, 68 FT.	EACH	3								1	1	1							
* 87700420	STEEL MAST ARM ASSEMBLY AND POLE, 70 FT.	EACH	2									1	1							
* 87702240	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 20 FT. AND 46 FT.	EACH	2									1	1							
* 87702370	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 26 FT. AND 44 FT.	EACH	1									1								
* 87702400	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 28 FT. AND 32 FT.	EACH	1									1								
* 87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	1					1												
* 87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1					1												
* 87703228	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 48 FT. AND 28 FT.	EACH	1											1						
* 87703230	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 60 FT. AND 28 FT.	EACH	1											1						
* 87703234	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 70 FT. AND 34 FT.	EACH	1							1										
* 87703260	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 70 FT. AND 40 FT.	EACH	1							1										
* 87704460	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 44 FT. AND 24 FT.	EACH	1					1												
* 87704556	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 56 FT. AND 16 FT.	EACH	1					1												
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	64					16	8	8	8	8	4	8	4					
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	24					4	4	4	4	4	4	4						
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	300					60	45	30	60	60		45						
* 87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	300					60	45	30	60	60		45						
* 87900200	DRILL EXISTING HANDHOLE	EACH	4											4						
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	98					9	14	14	14	15	15	1	15	1				
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	11					3	3	2	1	1	1							
* 88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	4					4												
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	9					1		2	2	1	1		2					
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	13					1		4	3	2	2		1					
* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	4								1	1	1		1					
* 88030250	SIGNAL HEAD, LED, 2-FACE, 1-4 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2						2											
* 88030260	SIGNAL HEAD, LED, 3-FACE, 1-4 SECTION, 2-5 SECTION, BRACKET MOUNTED	EACH	1							1										
* 88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	17						5	4	2	2	2		2					
* 88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	7						1		2	2	2							
* 88102760	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED	EACH	2						2											

* SPECIALTY ITEM ** Y030-1E 100% OAK BROOK
 NP NON-PARTICIPATING ITEM % Y080

FILE NAME = g:\CH07\0061\Road\SHETS\016012-SHT-50.dgn	USER NAME = jmg@lemba	DESIGNED - JMG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE. 1453	SECTION 55WRS	COUNTY	TOTAL SHEETS 362	SHEET NO. 8
PLOT SCALE = 5/8"=1'-0"	DRAWN - BAW	CHECKED - JRH	REVISED -			CONTRACT NO. 60D12				
PLOT DATE = 4/1/2010	DATE - 4/1/2010	REVISED -	SHEET NO. 8 OF 362 SHEETS			FED. ROAD DIST. NO. 7 [ILLINOIS] FED. AID PROJECT				