

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES 100% STATE	1000-2A					CODE NO	ITEM	UNIT	TOTAL QUANTITIES 100% STATE	1000-2A					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	91	91					*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8591	8591					
21400100	GRADING AND SHAPING DITCHES	FOOT	496	496					*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	652	652					
25100900	TURF REINFORCEMENT MAT	SQ YD	221	221					*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1148	1148					
28101400	RIPRAP	SQ YD	44	44					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	28	28					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15					*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	268	268					
40600300	AGGREGATE (PRIME COAT)	TON	73	73					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	241	241					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	28	28					*88600600	DETECTOR LOOP REPLACEMENT	FOOT	216	216					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	302	302					40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	719	719					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1534	1534					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	18261	18261														
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	261	261														
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	157	157														
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	105	105														
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	363	363														
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	419	419														
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100														
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3														
67100100	MOBILIZATION	L SUM	1	1														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2865	2865														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8591	8591														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	652	652														
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1148	1148														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	28	28														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4713	4713														
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182														

* SPECIALTY ITEMS