

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2009-074 I	COOK	12	3

CONTRACT 60H85

## GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E" AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.

THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS FOR THE PROTECTION OF EXISTING PETROLEUM PIPELINE WHEN WORKING AT LOCATION 1 (SN 016-0935) NEAR THE PIER 1 AND SHALL NOTIFY ONEOK NORTH PETROLEUM PIPELINE CO AT (888) 844-5658.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGES OF BURNHAM AND SKOKIE.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION, EXCEPT THE PIN DIAMETERS, AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847)705-4470 FOR ARTERIALS AND (847)705-4151 FOR EXPRESSWAYS A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTAINENCE BRIDGE INSPECTORS.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

THE "ARTERIAL ROAD INFORMATION SIGN (TC-22)" IS APPLICABLE ONLY TO ARTERIAL ROADS AND SHALL NOT BE APPLIED TO EXPRESSWAYS.

AT LOCATION 1: THE CONTRACTOR SHALL NOT BE ALLOWED TO CROSS ANY RAILROAD TRACKS. THE NORTH SLOPEWALL SHALL BE DONE FROM THE ABOVE.

AT LOCATION 2: THE CONTRACTOR SHALL SALVAGE AND RETURN THE EXISTING DRAIN PIPES TO:

DISTRICT BRIDGE OFFICE

1101 BIESTERFIELD RD

ELK GROVE VILLAGE, IL 60007.

CONTACT: SHAKER ASFOUR @ (847) 965-1501

THIS WORK SHALL INCLUDE REMOVING, TRANSPORTING AND UNLOADING THE EXISTING DRAIN PIPES TO THE ABOVE YARD. COST INCLUDED IN THE SLOPEWALL REPAIR.

SLOPEWALL SHALL BE REINFORCED WITH WELDED WIRE FABRIC 6 in x 6 in W4.0 X W4.0 WEIGHING 58 LBS PER 100 SQ.FT. COST OF THE MESH IS INCLUDED IN THE COST OF SLOPEWALL.

ILLINOIS DEPARTMENT OF  
TRANSPORTATION

GENERAL NOTES