

| SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | | SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | | | |
|-----------------------|---|--------|------------------|------------------------|--|--|--|--|-----------------------|-----------|---|------------------|------------------------|---------|--|--|--|--|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | | | | | | CODE NO | ITEM | UNIT | TOTAL QUANTITIES | | | | | | | |
| | | | | I000-2A | | | | | | | | | | I000-2A | | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 184 | 184 | | | | | | 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 1521 | 1521 | | | | | |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 184 | 184 | | | | | | 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 73 | 73 | | | | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 7 | 7 | | | | | | 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 3485 | 3485 | | | | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 34 | 34 | | | | | | 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 175 | 175 | | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS | TON | 13 | 13 | | | | | | 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 132 | 132 | | | | | |
| 40600826 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 344 | 344 | | | | | | 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 1656 | 1656 | | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 | | | | | | *78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 73 | 73 | | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 98 | 98 | | | | | | *78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 3485 | 3485 | | | | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 700 | 700 | | | | | | *78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 175 | 175 | | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 226 | 226 | | | | | | *78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 132 | 132 | | | | | |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 8333 | 8333 | | | | | | *78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 147 | 147 | | | | | |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 1100 | 1100 | | | | | | 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 133 | 133 | | | | | |
| 44003510 | MEDIAN REMOVAL PARTIAL DEPTH | SQ FT | 5542 | 5542 | | | | | | *88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 168 | 168 | | | | | |
| 44004610 | SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL) | SQ FT | 108 | 108 | | | | | | X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 51.4 | 51.4 | | | | | |
| 44201803 | CLASS D PATCHES, TYPE II, 13 INCH | SQ YD | 72 | 72 | | | | | | 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 20 | 20 | | | | | |
| 44201807 | CLASS D PATCHES, TYPE III, 13 INCH | SQ YD | 43 | 43 | | | | | | Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 20 | 20 | | | | | |
| 44201809 | CLASS D PATCHES, TYPE IV, 13 INCH | SQ YD | 29 | 29 | | | | | | 35501316 | HOT-MIX ASPHALT BASE COURSE, 8" | SQ YD | 20 | 20 | | | | | |
| 55039700 | STORM SEWERS TO BE CLEANED | FOOT | 214 | 214 | | | | | | 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 3 | 3 | | | | | |
| 60250200 | CATCH BASINS TO BE ADJUSTED | EACH | 2 | 2 | | | | | | 42300400 | PORTLAND CEMENT CONCRETE PAVEMENT, 8" | SQ YD | 20 | 20 | | | | | |
| 60252800 | CATCH BASINS TO BE RECONSTRUCTED | EACH | 1 | 1 | | | | | | | | | | | | | | | |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 2 | 2 | | | | | | | | | | | | | | | |
| 60257900 | MANHOLES TO BE RECONSTRUCTED | EACH | 1 | 1 | | | | | | | | | | | | | | | |
| 60300305 | FRAMES AND LIDS TO BE ADJUSTED | EACH | 12 | 12 | | | | | | | | | | | | | | | |
| 60300310 | FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) | EACH | 6 | 6 | | | | | | | | | | | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 3 | 3 | | | | | | | | | | | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | | | | | | | | | | | |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | | | | | | | | | | | | | | | |
| 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | L SUM | 1 | 1 | | | | | | | | | | | | | | | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | | | | | | | | | | | | | | |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 | | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|---|----------------------------|------------|-----------|---|--|--|--|--|--|--|--------------------|-----------|--------|--------------|-----------|
| FILE NAME = | USER NAME = sreedpa | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | | | | F.A.J. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| c:\pwwork\pwwork\steeppa\06982\0710-st-plan.dgn | | DRAWN - | REVISED - | | FAU 1362 (LAWRENCE AVE.)--FORSTER AVE. TO EAST RIVER RD. | | | | | | 1362 | 3200 RS-3 | COOK | 25 | 3 |
| | PLOT SCALE = 50,000' / IN. | CHECKED - | REVISED - | | SCALE: SHEET NO. OF SHEETS STA. TO STA. | | | | | | CONTRACT NO. 60J07 | | | | |
| | PLOT DATE = 2/2/2010 | DATE - | REVISED - | | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | | | | | | | | |