

SUMMARY OF QUANTITIES			90% FEDERAL, 10% STATE			SUMMARY OF QUANTITIES					
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BRIDGE X321-2A	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY	BRIDGE
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	29	29							
78300100	PAVEMENT MARKING REMOVAL	SQ FT	9060	9060							
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	8	8						
X0321468	PLUG EXISTING DECK DRAINS	EACH	32		32						
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4"	SQ YD	1369		1369						
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	89		89						
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	475		475						
X0325775	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	27,989	27,989							
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1							
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	30	30							
X5080600	MECHANICAL SPLICERS	EACH	85		85						
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	1369		1369						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	121		121						
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2							
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2							
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOUR</del>	<del>1000</del>	<del>1000</del>							
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	2	2							

\* SPECIALTY ITEMS  $\emptyset$ -4080

**LONGO, INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - MJY, DC	REVISED -
DATE - 01/29/2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
I-57 NB & SB OVER ABANDONED RR (12.8 MILES SOUTH OF US 30)**

SCALE: NONE SHEET NO. 4 OF 38 SHEETS STA. 939+74 TO STA. 943+21

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	99-2VB-I-1	WILL	38	4
D-91-215-10		CONTRACT NO. 60J25		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev.