

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY		BRIDGE	
					100% STATE	100% STATE	100% STATE	100% STATE
					CONSTRUCTION TYPE CODE 1000-2A	CONSTRUCTION TYPE CODE X231-2A	CONSTRUCTION TYPE CODE 1000-2A	CONSTRUCTION TYPE CODE X231-2A
	35501317	HOT-MIX ASPHALT BASE COURSE, 8 1/4"	SQ YD	187	187			
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19	19			
	44000100	PAVEMENT REMOVAL	SQ YD	187	187			
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	80	80			
	44002010	CONCRETE MEDIAN REMOVAL	FOOT	422	422			
	44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	60	60			
	44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	47	47			
	44213100	PAVEMENT FABRIC	SQ YD	107	107			
	44213200	SAW CUTS	FOOT	1022	1022			
	50102400	CONCRETE REMOVAL	CU YD	21.2			21.2	
	50157300	PROTECTIVE SHIELD	SQ YD	1,284			1,284	
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	23.4			23.4	
	50300260	BRIDGE DECK GROOVING	SQ YD	1,832			1,832	
	50300300	PROTECTIVE COAT	SQ YD	2,655			2,655	
	50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5,430			5,430	
	50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	28			28	
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,350			3,350	
	50800515	BAR SPLICERS	EACH	30			30	
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	182.0			182.0	
	52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	28			28	
	52100520	ANCHOR BOLTS, 1"	EACH	52			52	
	58700300	CONCRETE SEALER	SQ FT	5,695			5,695	
	60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	1,687		1,687		
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4		
	67100100	MOBILIZATION	L SUM	1		1		
	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1		1		
	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1		1		
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6		6		
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1996		1996		
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1590		1590		
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	1140		1140		
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1092		1092		
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,520		3,520		

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY		BRIDGE	
					100% STATE	100% STATE	100% STATE	100% STATE
					CONSTRUCTION TYPE CODE 1000-2A	CONSTRUCTION TYPE CODE X231-2A	CONSTRUCTION TYPE CODE 1000-2A	CONSTRUCTION TYPE CODE X231-2A
*	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	880		880		
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2,327		2,327		
*	78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	1,086		1,086		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20		20		
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12		12		
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	92		92		
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,951		2,951		
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32		32		
*	81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	30		30		
*	81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	1		1		
*	81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	240		240		
	X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4"	SQ YD	1,911			1,911	
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103		103		
*	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3		3		
	X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	18			18	
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	1,101			1,101	
	X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	9,000		9,000		
	X0326765	CLEANING AND PAINTING EXPOSED REBAR (SPECIAL)	SQ FT	50			50	
	X0326766	CLEAN AND RESEAL RELIEF JOINT	FOOT	129			129	
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1		1		
	X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	30		30		
	X8210305	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING	L SUM	1		1		
	Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	33.2			33.2	
	Z0006204	BRIDGE DECK HYDRO-SCARIFICATION, 1/2"	SQ YD	1,911			1,911	
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1		
	Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	5.0			5.0	
	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	5.5			5.5	
	Z0017100	DOWEL BARS	EACH	70		70		
	Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 2	EACH	2		2		
	Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	EACH	2		2		
	Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2		2		
	Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE) TEST LEVEL 3	EACH	2		2		

*Specialty Items

Rev.

FILE NAME =	DESIGNED - EJA	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME =	DRAWN - EJA	REVISED -				94	1010.1-1-2	COOK	37	3
PLOT DATE = 03/22/2010	CHECKED - AJP	REVISED -				SCALE: N.T.S.		SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.
	DATE - 3/19/10	REVISED -						CONTRACT NO. 60J30		