

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN I000				CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN I000			
				100% STATE								100% STATE			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	35	35											
25200110	SODDING, SALT TOLERANT	SQ YD	35	35				70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3500	3500			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	30				70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	460	460			
40600300	AGGREGATE (PRIME COAT)	TON	140	140				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	900	900			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	55	55				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	650	650			
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1405	1405				70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4950	4950			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	400	400			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	480	480				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15800	15800			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	200	200				* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3500	3500			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2860	2860				* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	460	460			
42001300	PROTECTIVE COAT	SQ YD	50	50				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	900	900			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	225	225				* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	650	650			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	34000	34000				* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	410	410			
44000600	SIDEWALK REMOVAL	SQ FT	225	225				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	382	382			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2344	2344			
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1190	1190				X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	612	612				Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	88	88			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	408	408											
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100											
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	74	74											
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10											
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6											
67100100	MOBILIZATION	L SUM	1	1											
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1											
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1											
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1											
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3700	3700											
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	400	400											
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15800	15800											

*Specialty Items

FILE NAME =	USER NAME = guilloumefp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\GUILLAUMEFP\075300\012250-01-plon.dgn	DRAWN -	REVISED -	0297			33-1	WILL	23	3	
PLOT SCALE = 50,0000 "/>										
PLOT DATE = 2/3/2010	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.			FED. ROAD DIST. NO. 1 (ILLINOIS) AID PROJECT		CONTRACT NO. 60J35		