

URBAN
80% FED.
20% STATE

SUMMARY OF QUANTITIES

URBAN
80% FED
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X020-2A STRUCTURE	1000-2A ROADWAY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	518	186	332
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	39	39	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	91	91	
44000100	PAVEMENT REMOVAL	SQ YD	808		808
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	1112	1112	
5002400	CONCRETE REMOVAL	CU YD	2.7	2.7	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2.7	2.7	
50300260	BRIDGE DECK GROOVING	SQ YD	170	170	
50300300	PROTECTIVE COAT	SQ YD	195	195	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	390	390	
60019200	CONCRETE MEDIAN, TYPE SB-6.00	SQ FT	7271		7271
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3		3
67100100	MOBILIZATION	L SUM	1		1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30		30
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3		3
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2559		2559
70400100	TEMPORARY CONCRETE BARRIER	FOOT	425		425
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	337.5		337.5
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4537.5		4537.5
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	100		100
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2		2
* 78100300	REPLACEMENT REFLECTOR	EACH	86		86
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	544		544
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1694		1694
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2		2
X0320887	POLYMER CONCRETE	CU FT	23.4	23.4	
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	184	184	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	116		116
X0322933	SILICONE JOINT SEALER, 2.5"	FOOT	97	97	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	42	42	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	38	38	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	7754		7754
X0712400	TEMPORARY PAVEMENT	SQ YD	808		808
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	184	184	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X020-2A STRUCTURE	1000-2A ROADWAY
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1.3	1.3	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE ID)	SQ YD	14.3	14.3	
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1		1
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1		1
58700300	CONCRETE SEALER	SQ FT	555	555	
44003100	MEDIAN REMOVAL	SQ FT	7271		7271

*Specialty Hems

FILE NAME =	USER NAME = #USER#	DESIGNED - SEW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES US ROUTE 14 (DEMPSTER STREET) OVER FARMERS CREEK				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - SEW	REVISED -			1324	3014-I	COOK	19	3				
	PLOT SCALE = #SCALE#	CHECKED - FML	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 60J40				
	PLOT DATE = #DATE#	DATE - 1/2010	REVISED -			ILLINOIS FED. AID PROJECT								