

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE I000-2A
20201006	GRADING AND SHAPING SHOULDERS	UNIT	215	215
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0	0
40600300	AGGREGATE (PRIME COAT)	TON	83	83
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	62	62
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	1,735	1,735
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	137	137
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	656	656
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,470	3,470
42001300	PROTECTIVE COAT	SQ YD	23	23
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	41,298	41,298
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2928	2928
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	248	248
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1,239	1,239
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	496	496
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	496	496
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,240	1,240
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,915	3,915
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	510	510
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46,690	46,690
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,736	1,736
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	121	121
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	529	529
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	109	109
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,521	2,521
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	510	510
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46,690	46,690
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,736	1,736
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	121	121
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	529	529
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	109	109
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	392	392
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	353	353
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	556	556
X0325866	CENTER LINE - RUMBLE STRIP	FOOT	6,378	6,378
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103

* SPECIALTY ITEM

1/28/2010 11:50 AM
 PLOT DATE = 1/28/2010
 PLOT SCALE = 1:50
 USER NAME = rjnhaska
 MODEL = Default



Excellence through Ownership

200 West Front Street
Wheaton, IL 60187

DESIGNED - MAK	REVISED - ---
DRAWN - DJW	REVISED - ---
CHECKED - MTH	REVISED - ---
DATE - 1/28/2010 5:12:39 PM	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

IL RTE 56 (BUTTERFIELD RD)

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. ___ OF 20 SHEETS STA. _____ TO STA. _____

F.A.P. RTE. 365	SECTION 59 RS-3	COUNTY DUPAGE	TOTAL SHEETS 20	SHEET NO. 3
CONTRACT NO. 60J49				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.