

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT		TOTAL QUANTITY	049-0037 SFTY-2A QUANTITY
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX D, N-90	TON	66	66	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	358	358	
42001300	PROTECTIVE COAT	SQ YD	227	227	
44001700	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	20	20	
50300260	BRIDGE DECK GROOVING	SQ YD	218	218	
59000200	EPOXY CRACK INJECTION	FOOT	29	29	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10	10	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2530	2530	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3502	3502	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	44	44	

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT		TOTAL QUANTITY	049-0037 SFTY-2A QUANTITY
* 78006110	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10	10	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	107	107	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6	6	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1215	1215	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	113	113	
X0320887	POLYMER CONCRETE	CU FT	7	7	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51	
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	227	227	
X0326766	CLEAN AND RESEAL RELIEF JOINT	FOOT	92	92	
X0325305	STRUCTURAL REPAIR CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	76	76	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	7950	7950	
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	13	13	
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	4	4	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	227	227	

* Specialty Items