SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES 100% STATE	CONSTRUCTION TYPE CODE I000-2A					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	998	998					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	599	599					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	400	400					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	318	318					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	54	54					
25200110	SODDING, SALT TOLERANT	SQ YD	54	54					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	54	54					
40600300	AGGREGATE (PRIME COAT)	TON	271	271					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	102	102					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2790	2790					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	751	751					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5681	5681					
42001300	PROTECTIVE COAT	SQ YD	99	99					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	67628	67628					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	323	323					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1271	1271					
55039700	STORM SEWERS TO BE CLEANED	FOOT	300	300					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12957	12957					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1076	1076					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	31178	31178					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES 100% STATE	CONSTRUCTION TYPE CODE I000-2A					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2029	2029					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	98	98					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	786	786					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	207	207					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14114	14114					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1076	1076					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	31178	31178					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2029	2029					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	98	98					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	786	786					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	207	207					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	708	708					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	601	601					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	250	250					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	7	7					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pwidot\galbannb\d0175346\D12490-sht-plan.dgn	USER NAME = galbannb	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 11/30/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. 83 (IVANHOE ROAD) FROM IL. 176 TO IL. 137
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
866	37 RS-4	LAKE	30	3
		CONTRACT NO. 60J59		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		