

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES 100% STATE	1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	62	62													
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5													
40600300	AGGREGATE (PRIME COAT)	TON	22	22													
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9													
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	258	258													
40600895	CONSTRUCTING TEST STRIP	EACH	1	1													
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	105	105													
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	527	527													
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	6268	6268													
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SO YD	30	30													
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	150	150													
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	45	45													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	228	228													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3													
67100100	MOBILIZATION	L SUM	1	1													
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	344	344													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8650	8650													
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8650	8650													
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	56	56													
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	15	15													
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4													

* SPECIALTY ITEMS

FILE NAME =	USER NAME = mlj/jo	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\mlj\jo\017645\DI2610-stt-plan.dwg	DRAWN -	REVISED -	2423					2009-119 RS	KANE	14	3	
PLOT SCALE = 50,000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 60J71									
PLOT DATE = 2/5/2010	DATE -	REVISED -	SCALE:					SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT	

Rev.